
February 15, 1995

**Bureau of Land Management** Warm Springs Resource Area 3500 East 500 North Fillmore, UT 84631

**SEVIER LAKE FEDERAL 1-29** SENE SECTION 29, T19S - R10W 2250' FNL, 700' FEL MILLARD COUNTY, UTAH



Chevron U.S.A. Production Company Western Exploration Division P.O. Box 1635

Houston, TX 77251

Attention: Mr. Rody Cox

#### Gentlemen:

For your consideration, please find in triplicate a Notice of Staking form for the subject well location. Chevron has proposed the drilling of a stratigraphic test to be commenced early in the second quarter 1995. Accompanying the Notice of Staking you will find a location plat for the proposed site.

As we advised, a surveyor has center-staked and corner-staked a 400 x 400' pad for the subject location. In addition, an archaeologist has completed a cultural resource inventory on the ground clearing the pad site, as well as a 200' buffer zone around the location. In my conversation with Mr. Cox, we have agreed to schedule the on-site surface inspection for February 28, 1995. Our plans may include visiting the site of each of the water wells (Mudhole and Headquarters wells) that are in the vicinity. We may use the water from either or both of the wells to drill the Sevier Lake test.

Further, this will serve as our formal request for an exception to the limitation specified in the oil and gas lease stipulation. Lease USA UTU-72587 stipulation allows exploration, drilling and other development activity in the N2, N2S2 of Section 29, T19S, R10W only during the period from July 1 to February 28 in order to protect crucial raptor nesting areas. Your office has indicated that a wildlife representative shall conduct an inventory of the drillsite to observe or determine occurrence of actual nesting during the season of ground raptor nesting activity. We request the Bureau's consideration in granting an exception to the limitation.

Chevron specifically requests that this information remain confidential. If you should require additional information with regard to this filing, please do not hesitate to contact this office. (713)754-7659.

Sincerely,

Annette Bak Landman Thrust Belt District

:me

via express mail delivery

BLM, State Director BLM, Richfield District


Utah Board of Oil, Gas & Mining

Mr. D. Haddock

Mr. J. Bailey

# NOTICE OF STAKING

NOTICE OF STAKING	6. Lease Number:		
(Not to be used in place of Application for Permit to Drill Form 3160-3)	USA UTU-72587		
1. Oil Well ( ) Gas Well ( ) Other (X)	7. If Indian, Allottee or Tribe Name:		
(Specify) Stratigraphic test to obtain stratigraphic information	n/a		
2. Name of Operator	8. Unit Agreement Name:		
Chevron U.S.A. Production Company, a Division of Chevron U.S.A. Inc.	n/a		
3. Specific Name/Number of Operator/Agent Chevron U.S.A. Production Company, a Division of Chevron U.S.A. Inc.	9. Farm or Lease Name USA		
4. Address & Phone No. of Operator/Agent P. O. Box 1635, Houston, TX 77251 (713)754-7659	10. Well No.: Sevier Lake Federal 1-29		
5. Surface Location at Well: 2250' FNL, 700' FEL Section 29	11. Field or Wildcat Name: Wildcat		
T 19 S, R 10 W	12. Sec., T., R., M., or Blk and Survey or Area SENE Section 29, T19S, R10W		
13. Formation Objective(s):	14. Estimated Well Depth: 5000'		
15. County, Parish or Borough Millard	16. State UTAH		
17. Additional information: See attachment - L	ocation map.		
The following items will be furnished with  A) Survey of Drilling Locatoin, pad layou  B) Drilling Plan with BOPE Diagram.  C) 13-Point Surface Use Plan with Cultur	it.		
D) Bond	-		
Occurrence of H2S is not anticipated duri	ng drilling program.		
18.Signed Mu Title:	Landman Date: 02/13/95		



Form 3160-3 (July 1992)

# SUBMIT IN TRIPLICATES

(Other instructions on reverse side)

FORM APPROVED OMB NO. 1004-0136 Expires: February 28, 1995

# UNITED STATES DEPARTMENT OF THE INTERIOR

	DEPARTMENT	OF THE INTE	RIOR		5. LEASE DESIGNATION	AND SERIAL NO.
BUREAU OF LAND MANAGEMENT					USA UTU-7258	7
APPL	ICATION FOR P	ERMIT TO DRIL	L OR DEEPEN		6. IF INDIAN, ALLOTTEI	OR TRIBE NAME
1a. TYPE OF WORK	ILL 🗓	DEEPEN			7. UNIT AGREEMENT N	AMB
b. TYPE OF WELL		ratigraphic ,			N/A	
OIL O	ELL OTHER TO		ONE ZONE	`L'	8. FARM OR LEASE NAME, WE	
2. NAME OF OPERATOR		a divis	ion of Chevron		SEVIER LAKE	FEDERAL 1-2
Chevron U.S.	A. Production Co	mpany, U.S.A.	Inc.		9. API WELL NO.	
3. ADDRESS AND TELEPHONE NO.	P.O. Box 1635 (713) 754-765 eport location clearly and	Houston, TX			10. FIELD AND POOL, O	B WILDCAT
At surface	00' FEL SECTION				11. SEC., T., B., M., OR I AND SURVEY OR AS	BLK.
At proposed prod. zor	ne				SEC. 29, T19S	
14. DISTANCE IN MILES	AND DIRECTION FROM NEAD	EST TOWN OR POST OFFI	:E*		12. COUNTY OR PARISH	
APPROX. 3/4 I	MI SE OF HWY 6/5	50			MILLARD	UTAH
15. DISTANCE FROM PROP	4580' EAST (	F SEC.   16. N	O. OF ACRES IN LEASE		OF ACRES ASSIGNED HIS WELL	
PROPERTY OR LEASE !	LINE, FT.   TA	(E   10	0,025.68		160 AC	
18. DISTANCE FROM PROI	OSED LOCATION®	19. r	ROPOSED DEPTH	20. ROTA	RY OR CABLE TOOLS	
TO NEAREST WELL, D OR APPLIED FOR, ON TH	RILLING, COMPLETED, N/A	1 7	,000'	ROT	ARY	
21. ELEVATIONS (Show wh	ether DF, RT, GR, etc.)				22. APPROX. DATE WO	EK WILL START
4555' GL					4/30/95	
23.		PROPOSED CASING AN	D CEMENTING PROGRA	м		
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	BETTING DEPTH		QUANTITY OF CEME!	(T
17.5"	13.375", H-40	48.0 #/FT	50'		SURFACE	
12.25"	9.625", K-55	29-3-7FT 36-7	1000'		RF W// 313 CF	
		3M BI	'	(265	SX)	

Be advised that Chevron U.S.A. Production Company is considered to be the Operator of Chevron Sevier Lake Federal #1-29, Millard Co., Utah, Lease USA-U72587, and is responsible under the terms and conditions of the lease for the operations conducted on the leased lands.

Oil Company of California and its co-principals) via surety consent	s wholly owned subsidiary Ch	o. U-89-75-81-34 (Standard evron U.S.A. Inc., as 3104.2.
N ABOVE SPACE DESCRIBE PROPOSED PROGRAM: 11 proposal i	is to despute a rive data on present productive zone and i	proposed new productive zone. If proposal is to drill or
N ABOVE SPACE DESCRIBE PROPOSED PROGRAM: It proposal is deepen directionally, give proment data on subsurface locations and me	assured and true vertical depths. Give blowout preventer	orogram, if any.
NABOVE SPACE DESCRIBEZPROPOSED PROGRAM: It proposes to deepen directionally, give perment data on subsurface locations and mes	assured and true vertical depths. Give blowout preventer	DATE3-13-95
Geepen directionally, give performed data on subsurface locations and measurement of the subsurface locations and subsurface locations and subsurface locations and subsurface locations and subsurface locations are subsurface locations are subsurface locations and subsurface locations are subsurface locations and subsurface locations are subsurface locations.	TITLE LANDMAN  APPROVAL DATE	DATE 3-13-95
deepen directionally, give perment data on subsurface locations and measurement.  A. BAR  (This space for Federal or State office use)	TITLE LANDMAN  APPROVAL DATE	which would entitle the applicant to conduct operations thereon.

API Number Assigned: 43-027-30035

E OF UTAH


			.i			
DIVISION OF OIL, GAS AND MINING					5. Lease Deelgnation and Se USA UTU-72587	
APPLICATION FOR PERMIT TO DRILL OR DEEPEN					6. If Indian, Allottee or Tribe N/A	Name:
1A. Type of Worlc	DRILL (X)	DEEPEN []			7. Unit Agreement Name: N/A	
B. Type of Well: OIL GAS OTHER: STRATIGRAPHICSINGLE ZONE MULTIPLE ZONE					8. Farm or Lease Name: SEVIER LAKE	
	CUTUDON II C A DOODICTION COMPANY 9 Well Number					
3. Address and Telephone Num	ber: P.O. BOX 1635 (713) 754-765	, HOUSTON, TX 77	/251		10. Field and Pool, or Wildow WILDCAT	±
4. Location of Well (Footages)					11. Qtr/Qtr, Section, Townshi	lp, Range, Meridian:
	FNL, 700' FEL SE (SAME)	C 29-T19S-R10W			SE4NE4, SEC. T19S-R10W	29
	(0/11/2)					13. State:
	on from nearest town or post office SE OF HWY 6/50				12. County: MILLARD	UTAH UTAH
15. Distance to nearest 458 property or lease line (feet):		16. Number of acres in lease: 10,025.68		17. Numbe 160	r of acres assigned to this well AC	: 
18. Distance to nearest well, drift completed, or applied for, or		19. Proposed Depth: 7000 <sup>1</sup>		20. Rotary ROT	or cable tools: ARY	
21. Elevations (show whether DF 4555 GL	F, RT, GR, etc.):				22. Approximate date work w 4/30/95	dii start
23.	DPAD.	OSED CASING AND	CEMENTING PROC	BRAM		
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUANTITY OF CEMEN	т
	13.375", H-40	48.0#/FT	50'	FROM S	URFACE	
17.5"	17.5			F W/313 CF		
17.5" 12.25"	9.625", K-55	29.3#/FT 36#/L	1000'			
		29.3#/FT 36#/	1000'	(265 S		
		29.5#/FT 36#/	1000'			
12.25"	9.625", K-55	JA 171		(265 S	x)	
12.25" DESCRIBE PROPOSED PROGRAM autosurface locations and measure	9.625", K-55  A: If proposal is to deepen, give did and true vertical depths. Give bit	ata on present productive zone and powout preventer program, if any.	proposed new productive zone. I	(265 S	X )  o drill or deepen directionally, (	
DESCRIBE PROPOSED PROGRAM aubsurface locations and measure  Be advised the	9.625", K-55  At: # proposal is to deepen, give did and true vertical depths. Give blat Chevron U.S.A	ata on present productive zone and p	proposed new productive zone. I Dany is consider	(265 S  *proposal is to red to JSA-U72	be the Operato	r of sponsible
DESCRIBE PROPOSED PROGRAM aubsurface locations and measured  Be advised th Chevron Sevie under the ter lands.  Bond coverage Oil Company o	9.625", K-55  M: # proposal is to deepen, give did and true vertical depths. Give by at Chevron U.S.A r Lake Federal # ms and condition for this well in a f California and	ata on present productive zone and a owout preventer program, if any.  Production Comp. 1-29. Millard Co.	proposed new productive zone. It oany is consider or the peration tionwide Bond No d subsidiary Cho for in 43 AFR	red to JSA-U72 is cond	be the Operato 587, and is reucted on the 1  -75-81-34 (Stales, as)	r of sponsible eased
DESCRIBE PROPOSED PROGRAM aubsurface locations and measured  Be advised th Chevron Sevie under the ter lands.  Bond coverage Oil Company o	9.625", K-55  M: # proposal is to deepen, give did and true vertical depths. Give by at Chevron U.S.A r Lake Federal # ms and condition for this well in a f California and	ata on present productive zone and gowout preventer program, Wany.  Production Compil-29, Millard Co. is of the lease for sprovided by Nathits wholly owned	proposed new productive zone. It oany is consider or the hease to or the operation tionwide Bond No d subsidiary Che for in 43 CFP	red to JSA-U72 is cond	be the Operato 587, and is reucted on the 1	r of sponsible eased ndard
DESCRIBE PROPOSED PROGRAM aubsurface locations and measured  Be advised th Chevron Sevie under the ter lands.  Bond coverage Oil Company o	9.625", K-55  M: # proposal is to deepen, give did and true vertical depths. Give by at Chevron U.S.A r Lake Federal # ms and condition for this well in a f California and	ata on present productive zone and gowout preventer program, Wany.  Production Compil-29, Millard Co. is of the lease for sprovided by Nathits wholly owned	proposed new productive zone. It oany is consider or the peration tionwide Bond No d subsidiary Che for in 43 (FP)	red to JSA-U72 is cond	be the Operato 587, and is reucted on the 1  -75-81-34 (Stalls.A. Inc., as DEVICE STALLS.A. OPERATOR OF THE STALLS.A. OPERATOR OPERATOR OF THE STALLS.A. OPERATOR OP	r of sponsible eased ndard
DESCRIBE PROPOSED PROGRAM aubsurface locations and measured  Be advised th Chevron Sevie under the ter lands.  Bond coverage Oil Company o	9.625", K-55  M: # proposal is to deepen, give did and true vertical depths. Give by at Chevron U.S.A r Lake Federal # ms and condition for this well in a f California and	ata on present productive zone and gowout preventer program, Wany.  Production Compil-29, Millard Co. is of the lease for sprovided by Nathits wholly owned	proposed new productive zone. It oany is consider or the operation tionwide Bond No d subsidiary Che for in 43 CFP OII DATE:	red to JSA-U72 is cond	be the Operato 587, and is reucted on the 1  -75-81-34 (Stalls.A. Inc., as DEVICE STALLS.A. OPERATOR OF THE STALLS.A. OPERATOR OPERATOR OF THE STALLS.A. OPERATOR OP	r of sponsible eased ndard

Approvat:

DIV OF OIL, GAS & MINING

E OF UTAH

FORM 3				•		
	DIVISION OF OIL, GAS AND MINING  5. Lease Designation and Serial Number: USA UTU-72587					
APP	6. If Indian, Allottee or Tribe Name: N/A					
1A Type of Work: DRILL [X] DEEPEN []					7. Unit Agreement Name: N/A	
B. Type of Well: O[L.	GAS OTHER: ST	RATIGRAPHIC <sub>SINGLE</sub>	ZONE MULTIPLE ZO	ONE []	8. Farm or Lease Name: SEVIER LAKE	
2. Name of Operator: CH	TEST  OUT VECAL IL C. A. DECENICATION COMPANY  9. Well Number:					
3. Address and Telephone N	lumber: P.O. BOX 1635 (713) 754-765	, HOUSTON, TX 7	7251		10. Field and Pool, or Wildo WILDCAT	at .
					11. Otr/Otr, Section, Townsh	nlp, Range, Meridian:
	FNL, 700' FEL SE	C 29-T19S-R10W		:	SE4NE4, SEC. T19S-R10W	29
At Proposed Producing Zo	···· (SAME)					
	ection from nearest town or post office AI SE OF HWY 6/50	<b>:</b>			12. County: MILLARD	13. State: UTAH UTAH
	80' EAST OF SEC	16. Number of acres in lease 10,025.68	:	I .	or of acres assigned to this we AC	<b>4</b> :
16. Distance to nearest well, completed, or applied for	driffling,	19. Proposed Depth: 7000		20. Rotary ROT	or cable tools: ARY	
21. Elevations (show whether 4555 GL	r DF, RT, GR, etc.):				22. Approximate date work 4/30/95	will start:
	PPOE	OSED CASING AND	CEMENTING PROC	GRAM		
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUANTITY OF CEMEN	VT .
17.5"	13.375", H-40	48.0#/FT	50'		URFACE	
12.25"	9.625", K-55	29.3#/FT 36#/L	1000'		F W/313 CF	
		sal 11		(265 S	)	<u></u>
		3111				
	RAM: If proposal is to deepen, give o	<u> </u>	t and a supplied to the same	V conceal is	o drill or deepen directionally.	give pertinent data on
Be advised	that Chevron U.S./ ier Lake Federal and erms and condition	A. Production Com 4. Production Com	npany is consider	red to USA-U72	be the Operato 2587, and is re	or of esponsible
Bond coverage for this well is provided by Nationwide Bond No. U-89-75-81-34 (Standard Oil Company of California and its wholly owned subsidiary Chevron U.S.A. Inc., as co-principals) via surety consent as provided for in 43 CFP 3104-20 BY THE STATE OF UTAH DIVISION OF OIL, GAS/AND MANING  DATE:  BY:						
24.	( ) / MI		- A.P.	WAX	EVAURAL Vans	3/3/95
Name & Signature:	1. Com		Title:Title:	40	E W 12 1 6	
epace for State use onl					MAR 2 3 1995	
API Number Assigned:	13-027-3003 <u>5</u>	<u></u>	Approval:	אומ	OF OIL, GAS & M	IINING



# LOCATION MAP

N89° 23'55" E 2,646.57' = Measured Bearing and Distance (N 89°12' E 2,640.0') = RECORD BEARING AND DISTANCE

N A

MAGNETIC DELINATION = 16'15' EAST
Basis of Bearing
Geodetic North ©
Black USC&GS 1957
N=039°02'51.342"
W=112°54'54.0526"
NAD 1927



SURVEYED UNDER MY DIRECTION

0 500 1000 1500 SCALE: 1" = 1000' U.S. SURVEY FOOT

C:\SURVEY\SEVIER\S29PLAT.DWG PLOT: STANDARD.PCP

APPLICATION FOR PERMIT
TO DRILL
CHEVRON PRODUCTION CO.
SEVIER LAKE FEDERAL
1-29 WELL
2,250' FNL, 701' FEL
SE1/4 OF NE1/4 SEC 29
T.19 S., R.10 W., SLB&M
MILLARD COUNTY, UTAH

REDCON INC.
655 EAST MEDICAL DRIVE, SUITE 150
BOUNTIFUL, UTAH 84010
(801) 298-2401 FAX (801) 298-2024
Drawn By: RAF | Date: MARCH 10, 1994
Bevined: | Date:

CONFIDENTIAL


**EXHIBIT 'B' - LOCATION PLAT** 

March 15, 1995

**Chevron** 

SEVIER LAKE FEDERAL 1-29 STRATIGRAPHIC TEST SENE SECTION 29, T19S-R10W MILLARD COUNTY, UTAH

Bureau of Land Management Richfield District 150 East 900 North Richfield, Utah 84701 Attention: Mr. Michael Jackson



Chevron U.S.A. Production Company Western Exploration Division P.O. Box 1635 Houston, TX 77251

#### Gentlemen:

The purpose of this is to submit for BLM approval the Application for Permit to Drill the subject stratigraphic test. The following items are submitted herewith in triplicate for the above location. We request that this information remain confidential.

- 1. APD Form 3160-3
- 2. Evidence of Bond coverage
- 3. Geologic Program
- 4. Drilling Program
- 5. Multipoint Surface Use Plan
- 6. Class III Cultural Resource/Archaeological Inventory
- 7. Surveyed Plats:
  - a. Exhibit "A" Vicinity Map
  - b. Exhibit "B" Location Plat
  - c. Exhibit "C" Pad Layout and Access Road
  - d. Exhibit "D" Well Pad Cross Section
  - e. Exhibit "E" Road Construction Detail
  - f. Exhibit "F" Rig/Facilities Location Plat
- 8. Hydrogen Sulfide Contingency Plan

Chevron is targeting April 30, 1995 as the anticipated start date for exploration operations in the event the exception to the wildlife stipulation and timing restriction is granted.

The mitigations (items 1-21) listed as an attachment to your correspondence of March 8, 1995 have been addressed in the APD. Your immediate review of Chevron's plans consistent with pertinent regulations and procedures would be appreciated.

If you have any questions regarding the submitted Application, please do not hesitate to contact me.

Sincerely,

Annette Bak Landman Thrust Belt District

ab/ encis


CC:

Rody Cox/BLM Warm Springs Resource Area State of Utah Division of Oil, Gas and Mining

- J. M. Bailey
- L. W. Stavert
- D. A. Haddock

E OF UTAH
DIVISION OF OIL, GAS AND MINING

	2				5. Lease Designation and 5 USA UTU-7258	
APPLICATION FOR PERMIT TO DRILL OR DEEPEN					6. If Indian, Allottee or Tribo N/A	Name:
1A Type of Work: DRILL [X] DEEPEN					7. Unit Agreement Name: N/A	
B. Type of Well: OIL	T GAS □ OTHER: ST	RATIGRAPHIC <sub>SINGLE</sub> ST	ZONE MULTIPLE Z	ONE 🗌	6. Farm or Lease Name: SEVIER LAKE	
2. Name of Operator: CHE		9. Well Number: FEDERAL 1-29	)			
3. Address and Telephone Nur	ivision of Chevr nber P.O. BOX 1635 (713) 754-765	, HOUSTON, TX 7	7251		10. Field and Pool, or Wild WILDCAT	cet:
4. Location of Well (Footages) At Surface: 2250 1 At Proposed Producing Zone	FNL, 700' FEL SE				11. Obs/Obs, Section, Towns SE4NE4, SEC T19S-R10W	
	tion from nearest town or post offici I SE OF HWY 6/50	<b>2</b> :			12. County: MILLARD	13. State: UTAH
15. Distance to nearest 458	15 Oktobre to page 4 4580 FAST OF SFC 16. Number of acres in lease:				er of acres assigned to this w AC	oli:
18. Distance to nearest well, d completed, or applied for,		19. Proposed Depth: 7000 <sup>1</sup>			ARY	
21. Elevations (show whether I	DF, RT, GR, etc.):				22. Approximate date work 4/30/95	will start:
23.	PROF	POSED CASING AND	CEMENTING PRO	GRAM		. <u></u>
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH		QUANTITY OF CEME	NT
17.5"	13.375", H-40	48.0#/FT	50'		SURFACE	
12.25"	9.625", K-55	29.3#/FT 36#/c	1000'	TO SU	RF W/313 CF	
12.20	3.023 , K 33	400 19		(265)	SX)	
		ANI				
subsurface locations and measur	AM: If proposal is to deepen, give or red and true vertical depths. Give to	MOMORE breatmer brodumin a min-				
Chevron Sevi under the te lands.	hat Chevron U.S., er Lake Federal rms and condition	#1-29, Millard Co ns of the lease <sup>.</sup>	for the operation	ons con	ducted on the	leased
Oil Company	e for this well of California an s) via surety co	d its wholly own	d for in 43 CFR	3164.2	0.3.A. IIIC., a	ATE
		•	O		S/ AND IMMI	
			DATE:	15	V) mittage	
	$\sim 1$			2071	Junior	
24. Name & Signature:	1. / Deh			ANTA	AEVOUEN VI	B375/95
space for State use only					MAR 2 3 1995	
•		-	Annual		MAK & S SOU	1
API Number Assigned:	3-027-3003 <u>3</u>	·	Approval:	DIV	OF OIL, GAS & N	/INING



# LOCATION MAP

N89° 23'55" E 2,646.57' = Measured Bearing and Distance (N 89°12' E 2,640.0') = RECORD BEARING AND DISTANCE



MAGNETIC DELINATION = 16'15' EAST
Basis of Bearing
Geodetic North @
Black USC&GS 1957
N=039°02'51.342"
W=112°54'54.0526"
NAD 1927

SURVEYED UNDER MY DIRECTION

0 500 1000 1500 SCALE: 1" = 1000' U.S. SURVEY FOOT

C:\SURVEY\SEVIER\S29PLAT.DWG PLOT: STANDARD.PCP

APPLICATION FOR PERMIT
TO DRILL
CHEVRON PRODUCTION CO.
SEVIER LAKE FEDERAL
1-29 WELL
2,250' FNL, 701' FEL
SE1/4 OF NE1/4 SEC 29
T.19 S., R.10 W., SLB&M
MILLARD COUNTY, UTAH

REDCON INC.
655 EAST MEDICAL DRIVE, SUITE 150
BOUNTIFUL, UTAH 84010
(801) 298-2401 FAX (801) 298-2024
Drawn By: KAF | Date: MARCH 10, 1994

CONFIDENTIAL

**EXHIBIT 'B' - LOCATION PLAT** 

# GEOLOGIC PROGRAM TERTIARY COREHOLE SEVIER LAKE PROSPECT

**Well Classification:** 

**Stratigraphic Test** 

**Surface Location:** 

700' FEL & 2250' FNL, Sec. 29-T19S-R10W

Bottom-Hole Location:

Straight hole.

**Elevation:** 

4,555' Ground Level

Objective:

To obtain stratigraphic information.

**Estimated Formation Tops:** 

Formation Name Depth (from GL)

Ancient Lake Bonneville Sediments surface
Tertiary Valley Fill near surface

Tertiary Basalt 1,400'
Tertiary Valley Fill 1,500'

Pre-Tertiary 2,500' to as deep as 7,000'

Possible Drilling Problems:

None anticipated. There is a possibility of lost circulation and hole caving if unconsolidated alluvial fan material is encountered. Shales and siltstones are the most likely lithology for most of the Tertiary section.

**Safety Precautions:** 

No H2S is anticipated. Several wells located east of the Cricket Range reported minor gas shows with H2S in some Paleozoic carbonates. Because we do not know what rocks underly the Tertiary sequence in our well, the possibility of H2S cannot be eliminated. There is a relatively small chance of encountering overpressured water or steam.

## Openhole Logs and Surveys:

We will run a complete suite of slim-hole logs.

Mud Logging:

Surface to TD with 2 man conventional mud-logging unit. Will also have consultant wellsite geologist present.

Cores: None planned.

## CHEVRON USA PRODUCTION CO.

# SEVIER LAKE FEDERAL #1-29 700' FEL & 2250' FNL SEC 29-T19S-R10W MILLARD COUNTY, UTAH

# **EIGHT POINT DRILLING PLAN**

# 1. ESTIMATED FORMATION TOPS:

Ancient Lake Bonneville Sediments	Surface
Tertiary Valley Fill	Near Surface
Tertiary Basalt	1,400'
Tertiary Valley Fill	1,500'
Pre-Tertiary	2,500'
Precambrian	7,000'

# 2. <u>ESTIMATED DEPTHS OF TOP AND BOTTOM OF WATER, OIL, GAS, OR OTHER MINERAL BEARING FORMATIONS AND PLAN FOR PROTECTION:</u>

**Deepest Fresh Water:** ~700' based on depth of existing water wells in area used for the purpose of watering livestock.

Oil Shale: None Expected.

Oil: Possible oil below the Tertiary Basalt.

Gas: Possible gas below the Tertiary Basalt.

Protection of oil, gas, water, or other mineral bearing formations: Protection shall be accomplished by cementing surface casing back to the surface or to depths sufficient to isolate required formations. This well is a stratigraphic test and will be plugged and abandoned upon completion of drilling and logging operations. There is no intent to produce this well. Please refer to casing and cement information for protection plans.

# 3. PRESSURE CONTROL EQUIPMENT:

For drilling conductor hole to 50': No BOP equipment required.

For drilling surface hole to 1,000':

No BOP equipment required. Rotating head for air drilling only.

For drilling through 9.625" surface casing to TD:

Maximum anticipated surface pressure is <2590 psi.

Pressure control equipment shall be in accordance with BLM minimum standards for 3000 psi equipment.

A casing head with an 11", 3000 psi flange will be screwed or welded onto the 9.625" surface casing.

BOP stack will consist of a double gate and annular preventer. The double gate will be equipped with pipe rams on bottom and blind rams on top. The choke and kill lines will be connected to outlets between the bottom and top rams, utilizing either the ram body outlet or a drilling spool with side outlets. The BOP stack will be 9" or 11" bore, 3000 psi working pressure or greater. The choke and kill lines will be 2" or 3" bore, 3000 psi working pressure or greater. Please refer to attached schematics.

A rotating head will be used while drilling below surface casing to facilitate using air, air/mist, stiff foam or aerated mud as a circulating medium.

Test procedure and frequency shall be in accordance with BLM minimum standards for 3000 psi equipment.

# 4. SUPPLEMENTAL DRILLING EQUIPMENT AND CASING INFORMATION:

Casing Information: All casing except 13 3/8" will be new pipe and tested to 1500 psi. The 13 3/8" will not be tested.

Casing	Weight	Grade	Conn.	Stage	Centralizers
13.375"	48.0 #/ft.	H-40	STC	No	No
9.625"	29.3 #/ft.	K-55	STC	No	*

<sup>\*</sup> Centralizers will be placed 10' above shoe, on 1st, 3rd, 5th and last collars.



## **Cement Information:**

Casing	Cement
13.375"	Cemented from surface utilizing Ready-Mix.
9.625"	Oilfield type cement circulated in. Class "A" w/ 2% CaCl <sub>2</sub> single slurry mixed to 15.6 ppg, yield = 1.19 cf/sx. Fill to surface with 313 cf (265 sx) calculated. Tail plug used. Allowed to set under pressure.

Upon completion of drilling and logging operations, well will be abandoned. Abandonment plugs will be of Class "A" neat slurry. Size and location of plugs will be determined at conclusion of logging.

# **Drilling Equipment:**

Conductor hole will be drilled and conductor casing set with small rotary surface hole rig.

Drilling below conductor casing will be with conventional rotary equipment equipped to use air, fluid or a combination of both.

# 5. <u>CIRCULATING MEDIUM, MUD TYPE, MINIMUM QUANTITIES OF WEIGHT MATERIAL, AND MONITORING EQUIPMENT:</u>

Surface hole will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below surface casing will be with air, air/mist, stiff foam or aerated water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash, and polymers. No chromate's will be used. It is not intended to use oil in the mud, however, in the event it is used, oil concentration will be less than 4% by volume. Maximum anticipated mud weight is ±9.0 ppg.

No minimum quantity of weight material will be required to be kept on location. Sufficient quantity of water to load the hole while air drilling will be on location and readily available at all times.

PVT/Flow Show will be on location and operable from base of conductor casing to TD in the event fluid drilling is incorporated.

Gas detector will be used from surface (depth mud loggers on) to TD.

# 6. ANTICIPATED TYPE AND AMOUNT OF TESTING, LOGGING, AND CORING:

Logging:

Mud logging:

Electric Logging:

Surface to TD

A complete suite of open hole

logs will be run.

Coring:

None planned but are possible.

**Testing:** 

None planned but are possible.

# 7. EXPECTED BOTTOM HOLE PRESSURE AND ANY ANTICIPATED ABNORMAL PRESSURE, TEMPERATURES, OR OTHER HAZARDS (H2S, STEAM, ETC.) AND ASSOCIATED CONTINGENCY PLANS:

Normal pressure gradient to TD. Some slightly pressured gas zones (.45-.47) may exist below the Tertiary Basalt. All zones are anticipated to be tight - drill underbalanced with air, air/mist, stiff foam or aerated fluids. If any Hydrogen Sulfide/Steam is encountered, air drilling will be discontinued and drilling mud will be used exclusively from that point to completion of the well

Maximum expected BHP @ 7000':

~3290 psi (0.47 psi/ft.).

Maximum expected BHT @ 7000': ~135° F


# 8. OTHER:

If large quantities of water are encountered during air drilling operations, any clear fluid containing no solids or hydrocarbons will be spread on location and neighboring dirt/gravel roads in an effort to control dust.

# CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL-CONTROL AND BLOWOUT PREVENTION

# E. CLASS III BLOWOUT PREVENTER STACK:

The Class III preventer stack is designed for drilling or workover operations. It is composed of a single hydraulically operated annular preventer on top, then a blind ram preventer, a drilling spool, and a single pipe ram preventer on bottom. The choke and kill lines are installed onto the drilling spool and must have a minimum internal diameter of 2". All side outlets on the preventers or drilling spool must be flanged, studded, or clamped. An emergency kill line may be installed on the wellhead. A double ram preventer should only be used when space limitations make it necessary to remove the drilling spool. In these instances, the choke manifold should be connected to a flanged outlet between the preventer rams In this hookup, the pipe rams are only. considered master rams only, and cannot be used to routinely circulate out a kick. Class III blowout preventer stack is shown to the right in Figure 11J.4.




Rev 10/91

# CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL CONTROL AND BLOWOUT PREVENTION

## D. CLASS III CHOKE MANIFOLD

The Class III choke manifold is suitable for Class III workovers and drilling operations. The Standard Class III choke manifold is shown in Figure 11J.8 below. Specific design features of the Class III manifold include:

- The manifold is attached to a drilling spool or the top ram preventer side outlet.
- 2. The minimun internal diameter is 2" (nominal) for outlets, flanges, valves and lines.
- Includes two steel gate valves in the choke line at the drilling spool outlet. The inside choke line valve may be remotely controlled (HCR).
- Includes two manually adjustable chokes which are installed on both side of the manifold cross.
   Steel isolation gate valves are installed between both chokes and the cross, and also downstream of both chokes.
- 5. Includes a blooey line which runs straight through the cross and is isolated by a steel gate valve.
- Includes a valve isolated pressure gauge suitable for drilling service which can display the casing pressure within view of the choke operator.
- Returns through the choke manifold must be divertible through a mud-gas seperator and then be routed to either the shale shaker or the reserve pit through a buffer tank or manifold arrangement.
- If the choke manifold is remote from the wellhead, a third master valve should be installed immediately upstream of the manifold cross.




# CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL CONTROL AND BLOWOUT PREVENTION


# D. TYPE "B" KILL LINE — CLASS III, IV , AND V WELLS

The type B kill line described below in Figure 11J.11 is the minimum recommended hookup for installation on all Class III, Class IV and Class V wells. Specific design features of the type B kill line include:

- The preferred kill line connection to the well is at the drilling spool, however, a preventer side outlet
  may be used when space restrictions exclude the use of a drilling spool. In all cases, the kill line
  must be installed below the uppermost blind rams so the well can be pumped into with no pipe
  in the hole.
- 2 The arrangement includes two 2" (nominal) gate valves installed at the drilling spool and an upstream fluid cross. The outside valve may be hydraulically remote controlled.
- 3. Two pump-in lines should be attached to the fluid cross. The primary kill line should be routed to the rig standpipe where it can be manifolded to the rig pumps. The remote kill line should be run to a safe location away from the rig or to the rig cementing unit. The remote kill line should have a loose end connection for rigging-up a high pressure pumping unit.
- 4. Both the primary kill line and the remote kill line must include a 2" check valve which is in working condition while drilling. If a check valve is crippled for testing purposes, the flapper or ball must be re-installed and tested before drilling resumes.
- The primary kill line must include a pressure gauge which can display the pump-in pressure on the rig floor.
- 6. Any lines which are installed at the wellhead are designated as "emergency kill lines" and should only be used if the primary and remote kill lines are inoperable.



表がまれるがある。これではまればないであるとのではないながないないです。これではないとうでは、これでは、これないないというできないという。 そのではれるがあるというではまればないできないできないできない。



## **MULTIPOINT SURFACE USE PLAN**

CHEVRON U.S.A. INC.
SEVIER LAKE FEDERAL #1-29
STRATIGRAPHIC TEST
SECTION 29, T19S, R10W
MILLARD COUNTY, UTAH

#### 1. PROPOSED FACILITIES

- A. This well to be drilled as a stratigraphic test only. There will be no permanent facilities associated with this well.
- B. A blooie pit approx. 100' X 50' X 10' with a 30' high back wall will be constructed approximately 150' from center hole. This pit will be located directly behind and share a common wall with the conventional reserve pit. SEE EXHIBIT "F".

#### 2. LOCATION AND TYPE OF WATER SUPPLY

A. Two (2) Government facilities may be used for obtaining water:

(i) Facility Name: Mudhole Water Well

Location: SWSW Section 29 - T19S, R9W

Millard County, Utah

(ii) Facility Name: Headquarters Water Well

Location: SESE Section 15 - T19S, R9W

Millard County, Utah

A BLM form water use permit will be used for this purpose.

B. An alternative source for obtaining water will be to appropriate water from the Sevier River from a location within approximately two (2) miles of the stratigraphic test located at a point in the SWSE Section 22, T19S - R 10W. A State of Utah Application to Appropriate Water (Form 97) will be used for this operation.

The transportation method for all water to be used in drilling the proposed well will be determined; and, any access roads that are used to haul or transport the water shall be appropriately described and the necessary R/W permits shall be filed and provided to authorized officer of the BLM.

#### 3. METHODS FOR HANDLING WASTE DISPOSAL

- A. Cuttings will be settled out in either the conventional reserve pit or the blooie pit (while drilling with air). Both pits will be lined with bentonite liners. The pit system will be fenced in accordance with BLM standards.
- B. Drilling fluids will be retained in reserve pits utilizing maximum recirculation during drilling operations. Following drilling, the liquid waste will be evaporated, then the reserve pit will be backfilled and returned to grade.

During air drilling, a "dust killing" mechanism will be employed to minimize the amount of dust actually released to the atmosphere. This dust & cuttings will be discharged into the reserve pit and disposed of as above.

C. Sewage will be disposed of in fiberglass insulated holding tanks which will be placed in the vicinity of the trailers. The sewage will be hauled to an approved disposal site. Less than 1500 gallons of waste water per day will be hauled and treated. The appropriate sanitation permits will be obtained from the Six County Sanitation and Health Department.

D. Trash will be contained in a portable metal container and hauled periodically to an approved landfill.

#### 4. ANCILLARY FACILITIES

A. Six to eight trailers will be placed on the drilling location to house the tool pusher, drilling representative, mud engineer, mud logger, geologist, air operators, hammer operator and jet nozzle operator. Refer to Exhibit "F" for rig/layout facilities detail.

#### 5. WELLSITE LAYOUT

- A. The top eight inches of topsoil will be removed from the location and stockpiled. Location of mud tanks, reserve and blooie pits, pipe racks, air compressors, living facilities and soil stockpiles are shown on the attachments marked Exhibits "C", "D" and "F".
- B. All pits will be lined with a bentonite liner.
- C. Access to the well pad will be as indicated on Exhibits "A" and "C".

# 6. PLANS FOR RESTORATION OF SURFACE

- A. All surface areas will be graded to as near to the original condition as possible and contoured to maintain possible erosion to a minimum. Any rock encountered in excavation will be disposed of beneath backfill to return the surface to its present appearance and provide soil for seed growth.
- B. The topsoil will be evenly distributed over the disturbed area and reseeded.
- C. Pits and any other area that would present a hazard to wildlife or livestock will be fenced off when the rig is released and removed.
- D. Any oil accumulation on the pit will be removed or overhead flagged as dictated by then existing conditions.
- E. Rehabilitation will commence following release of the rig and drying of the pits. The wellsite will be abandoned and all disturbed areas will be recontoured to the natural contour as is possible.

# 7. DESCRIPTION OF THE PROJECT AREA AND EXISTING ROADS

- A. Sevier Lake Federal 1-29 occupies a small (400' x 400') area just north of the northeastern shore of the Sevier Lake and northwest of Bitterweed Lake. Access to the pad is from an existing unimproved BLM road which is approximately 20 feet south of the well pad's southern boundary.
- B. Twenty (20) feet of access road will be constructed from the existing BLM road onto the proposed well site as indicated on Exhibits "A" and "C".
- C. The two-track existing, unimproved road will need to be upgraded or improved in certain areas. Some minor maintenance may be necessary. Chevron will obtain the appropriate written agreements and/or permits as necessary to use existing roads or authorized rights of way. Documentation will be submitted prior to APD approval.

#### 8. TOPSOIL SALVAGING

As required by BLM, Chevron will strip topsoil and stockpile topsoil separately from spoils storage. All available topsoil will be salvaged. During topsoil salvaging, at least eight inches and up to twelve inches of topsoil will be salvaged.

#### 9. EROSION AND SEDIMENT CONTROLS

- A. Revegetation, Erosion and Sediment Control. During reclamation of the right-of-way, Chevron will be responsible for assuring compliance with all reclamation requirements. Chevron will use the reclamation and erosion control procedures that are outlined in this plan and according to BLM requirements. However, because field conditions encountered during construction and reclamation cannot be precisely predicted, this plan could be modified to accommodate field conditions and local features encountered.
- B. Recontouring. All graded areas will be recontoured to blend into the surrounding landscape and to reestablish the natural drainage patterns. Emphasis during recontouring will be to return the entire right-of-way to its original contour, to stabilize slopes, to control surface drainage and to provide a more aesthetic appearance. Ruts and other scars will be filled.
- C. Scarification. Prior to respreading, the right-of-way will be scarified by ripping or chiseling to loosen areas compacted by equipment traffic. Scarifying the subsoil will also promote water infiltration, better soil aeration and root penetration. In sloping areas, scarification is important to provide a rough interface between the topsoil and subsoil to reduce the potential for soil slippage.
- D. Soil Replacement. All topsoil salvaged will be uniformly spread over the portions of the right-of-way from where the soil was salvaged. If compaction occurs during this operation, the compacted area will be scarified. Topsoil spreading will not occur during wet periods when soils are easily compacted and the construction contractor will prohibit all travel over retopsoiled areas.
- E. Erosion Controls. Waterbars will be used on slopes to reduce erosion from concentrated surface runoff. Waterbars will be spaced depending on oil type and slope grade and other site-specific conditions such as proximity to streams. However, a general spacing guideline will be according to the following criteria:

Grade (%)	Interval (feet)
< 5	none
5-10	150
11-20	100
21-30	75
> 30	50

Waterbars will also be installed at significant grade changes and other appropriate areas along with areas requested by the land management agency. Waterbars will be constructed to drain at approximately a 2% grade, be cut to a minimum of 12 inches in depth below the surface and will originate and end in stable vegetated areas.

If warranted, diversion dikes will be installed at the top of slopes to divert runoff away from slopes. These dikes will be constructed to a height of 1.5 feet or greater, have a top width of two feet, have side slopes flatter than 2:1 and should be compacted to 85% of maximum density. Discharge from these dikes will be to vegetated areas or other stables areas or drainage system.

Another important component of erosion and sediment control is to scarify the right-of-way to relieve any compaction and to promote infiltration by reducing runoff. Mulching will also be used on all steep slopes to reduce erosion potential.

Straw bales, silt fences or earth dikes will be placed on the stream-side of the right-of-way where it is adjacent to an intermittent or perennial drainage. Where trenches are constructed across intermittent drainages with the potential to carry sediment to perennial waters, silt catchment dams will be installed. Where necessary, permanent trench breakers would be installed on steep slopes.

- F. Final Reclamation. The reclamation practices outlined in this section will occur on all areas to be seeded. The areas of the right-of-way to be seeded included all graded areas and scalped portions of the right-of-way. Chevron and/or BLM may require seeding of other areas where the vegetative cover has been reduced to a level that may result in erosion or weed invasion.
- G. Seedbed Preparation. Seedbed preparation will be conducted immediately prior to seeding to prepare a firm seedbed conducive to proper seed placement and moisture retention. Seedbed preparation will be performed to break up surface crusts and to eliminate weeds which may have developed between initial reclamation and seeding. In most areas chisel plowing will be used to achieve this surface.
- H. Fertilization. In general, fertilizers will not be added to the right-of-way. If fertilizers are applied, they will be applied during the maintenance period as determined by a professional agronomist. Fertilizers will not be applied to mulched areas within 100 feet of a drainage.
- I. Seed Mixtures. Seed mixtures would be approved by the BLM. Seeding rates will be based on pure live seed. To the extent possible, local sources will be used to supply the seed. Where appropriate, shrub species will be incorporated into seed mixes. Native species of vegetation will also be reestablished by topsoil salvaging.
- J. Seeding Timing. Seeding is anticipated to occur prior to prolonged ground frost, depending on field moisture conditions. Seeding is to be accomplished late enough in the fall so that seeds do not germinate until the following spring. If field conditions in the fall are not conducive for seeding, spring seeding will occur. Spring seeding will be accomplished as early as possible to allow equipment operation without soil damage. If spring seeding is to occur, every effort will be made to prepare the area in the fall so that seeding is not delayed. Mulching will take place in the fall so that disturbed surfaces are protected from erosion during the winter and spring.
- K. Seeding Methods. Drill seeding will occur on all areas except on slopes having greater than 33% grades on soils having significant surface rock. Drilling will be done on the contour as much as possible. In areas where erosion control and water conservation are required or where drilling on the contour is not feasible, broadcast seeding will be used. The seeding rate will be doubled where broadcast and the seed will be lightly covered by dragging with a chain or by hand raking.
- L. Mulching. A weed free straw or hay mulch will be applied to the soils at an application rate of two tons per acre to reduce erosion and to enhance seedling establishment on required slopes.

To reduce sedimentation at streams and drainages, matting on each bank will occur for approximately 100 feet or as necessary based on site-specific conditions. A jute thatching or bonded fiber blankets or mats will be used to stabilize seeded areas. These mats will be securely anchored with pegs or staples. If construction is completed more than 30 days prior to seeding, these areas will be mulched immediately after construction for temporary erosion control

M. Temporary Erosion Control. Temporary sediment barriers, such a silt fences made from geotextile fabric or straw bales, will be erected during construction at the base of slopes at the stream crossings. These structures and temporary waterbars or slope breakers will be constructed where appropriate as determined by the BLM. If needed, spacing of waterbars will occur at the following intervals:

Slope (%) Spacing (feet) 300 200

Erosion control structures will be repaired on a daily basis during construction and will be maintained until revegetation efforts prove successful.

# 10. MATERIALS HANDLING AND SPILL PREVENTION, CONTAINMENT AND CONTROL

#### A. Introduction

It is Chevron's intent to minimize potential for a spill and to contain any spillage to the smallest area possible and to protect areas which are considered environmentally sensitive (i.e., in the vicinity of drainage's, groundwater wells). It is the policy of Chevron to comply with all environmental and safety laws and regulations and to provide training and equipment designed to prevent pollution. It is Chevron's intent that everything practical be done to minimize the potential for and consequences of a spill during construction activities.

B. Hazardous Materials Used During Construction and Spill Prevention Measures.

Potential spills from construction are limited primarily to: 1) diesel used to fuel construction equipment; and (2) lubricating oils used by construction equipment.

To prevent these materials from reaching waterways, hazardous substances, chemicals, fuels and lubricating oils will not be stored within 100 feet of drainages, stream banks or wetlands. No construction equipment refueling or maintenance will be allowed within 100 feet of any drainage, stream bank or wetland. In addition, areas within 200 feet of groundwater wells would not be utilized for these activities.

Any fuel storage tanks will be located inside earthen diked berms designed to hold 1.5 times the capacity of the largest tank within the berm. The diked area will incorporate a compacted clay or artificial liner in its design. The tank will be set directly on the liner. Non-abrasive padding may be used under the tank to provide stability as long as the integrity of the liner is not compromised. The purpose of this liner is to protect soils located under the tank or used in dike construction from contamination. Any spilled materials located on the liner will be removed prior to dismantling the tank and dike.

Prior to their use, the construction contractor will visually inspect fuel storage tanks for cracks, excessive corrosion or other flaws which may compromise the integrity of the tank. Hoses and valves will be similarly inspected. If the construction contractor determines that the equipment is in good mechanical condition, it may be moved onto the construction right-of-way. Otherwise, the equipment will be rejected and alternative equipment in good condition employed. Each tank will be similarly inspected as it is moved down the construction right-of-way. The construction contractor will keep a written record of tank and associated equipment inspections onsite during construction. At the completion of construction, the tank inspection records will be provided to Chevron.

In addition, the construction contractor will inspect the integrity of all dikes and the liner at least twice daily and repair the dikes or replace the liner immediately if they become breached



or torn. Catch basins will be installed at each of the refueling locations to collect residual materials which may drain from hoses used to fuel the construction equipment. Materials collected in the catch basin or spillage collected in the liner will be disposed at a state approved disposal facility or recycled. It is preferable to locate these catch basins within the bermed dike, however, they need to be protected from overflow from storm water.

Precipitation in the region is relatively low. However, if storm water accumulates it may be necessary to drain it from within the diked area containing fuel storage tanks. If the storm water has been contaminated with diesel fuel or other pollutants, all water will be removed by vacuum truck or similar means and hauled to a disposal facility approved by the State of Utah. However, if no oil sheen is present and there are no other visible signs of pollution, the storm water may be left to evaporate within the dike after the tank has been removed. Under no circumstances will the construction contractor allow the surface discharge or other release of water contained within the diked area without the prior approval of the environmental representative of Chevron.


Construction equipment maintenance requiring the draining and replacement of fluids will occur only on areas of the right-of-way approved by Chevron. Before lubricants are drained from the construction equipment, a layer of at least 12-mil lubricants are drained from the construction equipment, a layer of at least 12-mil plastic liner will be placed under the equipment to collect any spilled material. Spilled material will be drained from the liner and disposed with the fluids removed from the construction equipment. Under no circumstances will the construction contractor allow material from the liner to spill on the ground surface.


Any soils contaminated by fuels, lubricating oils or other hazardous materials will be cleaned up, removed from the right-of-way and either treated by an approved contractor or hauled to an approved disposal site.

If necessary, Chevron would collect samples of soil strata below the spill to assure that all hydrocarbon contaminated soils have been removed from the site. All materials used to clean up the spill will be double bagged and inspected prior to removal from the spill site. All vegetation contaminated by the spilled material will be similarly collected, bagged and disposed at an approved disposal facility.

# 11. FINAL STABILIZATION AND MAINTENANCE

Implementation of measures described earlier are designed to assure that final stabilization and minimization of off-site discharges and sedimentation is achieved. If reseeding is judged to be necessary, this plan will be reviewed for any necessary changes needed to improve revegetation success. Maintenance of all temporary and permanent erosion control structures or procedures will occur annually where needed and until revegetation is deemed successful. If rills develop that are greater than six inches in depth, they will be filled and the area will be reseeded and mulched. Additional erosion control structures or procedures will also be implemented if erosion problems exist that are not properly treated with existing practices.





RESERVE PIT VOLUME

BELOW 2 FT FREEBOARD = 2800 BBLS WITHIN 2 FT FREEBOARD = 1200 BBLS
TOTAL = 4000 BBLS

BASIS OF ELEVATION
USC&GS MON. "SODA" 1957, PID KO0436

ELEV. 4583.0 NAVD 1988

FINISHED PAD ELEVATION TO BE 4553.70

**QUANTITIES** 

TOPSOIL EXCAVATION (2" THICK) = 566 CY EXCAVATION EXCLUDING PIT = 363 CYPIT EXCAVATION = 861 CYTOTAL TOPSOIL & EXCAVATION = 1790 CY = 140 CY EXCESS MATERIAL = 1650 CY

FILL CONSTRUCTION COMPACT TO 95% OF AASHTO T-99 DENSITY IN 8" MAXIMUM LOOSE LIFTS


ALL CUT AND FILL SLOPES ARE 1.5:1


CHEVRON PRODUCTION CO. SEVIER LAKE FEDERAL 1-29 WELL PAD LAYOUT AND ACCESS ROAD SE 1/4 OF NE 1/4 SECTION 29 T.19 S., R.10 W., SLB&M MILLARD COUNTY, UTAH

REDCON INC. 655 EAST MEDICAL DRIVE, SUITE 150 BOUNTIFUL, UTAH 84010 (801) 298-2401 (801) 298-2024 FAX

DATE: 3-10-95
FILE: C:\SURVEY\SEVIER\SEC29.DWG
DRAWN: K. ENGSTROM JOB NO: U/534/AE-8 PLOT: STANDARD.PCP

200





SCALE: HORIZONTAL: 1" = 100' VERTICAL: 1" = 10'

ALL CUT & FILL SLOPES ARE 1.5 : 1




NOT VALID UNLESS SIGNED

CHEVRON PRODUCTION CO.
SEVIER LAKE FEDERAL 1-29 WELL
WELL PAD CROSS SECTIONS
MILLARD COUNTY, UTAH

REDCON INC. 655 RAST MEDICAL DRIVE, SUITE 150 BOUNTIFUL, UTAH 84010 (801) 298-2401 (801) 298-2024 FAX

DATE: 3-10-95
FILE: C:\SURVEY\SEVER\SEC29SEC.DWG
DRAWN: K: ENGSTROM
JOB NO: U/534/AE-8
PLOT: STANDARD.PCP

EXHIBIT 'D' - WELL PAD CROSS SECTION



# TYPICAL ROADWAY SECTION

CUT/FILL TABLE				
CUT/FILL	SLOPE RATIO			
0' TO 4'	4:1			
4' TO 10'	3:1			
OVER 10'	2:1			

NOTE:
1. CRUSHED GRAVEL TO BE UTAH D.O.T. SECTION 301, 1" MINUS GRAVEL COMPACTED TO 4" THICKNESS TO 95% AASHTO T-99 DENSITY.

2 EARTH FILL AND TOP ONE FOOT SUBGRADE COMPACTED TO 95% AASHTO T-99 DENSITY IN 8" MAXIMUM LOOSE LIFTS.



NOT VALID UNLESS SIGNED

CHEVRON PRODUCTION CO.
SEVIER LAKE FEDERAL 1-29 WELL
ROAD CONSTRUCTION DETAILS
MILLARD COUNTY, UTAH

REDCON INC. 655 EAST MEDICAL DRIVE, SUITE 150 BOUNTIFUL, UTAH 84010 (801) 298-2401 (801) 298-2024 FAX

DATE: 3-10-95
FILE: C:\SURVEY\SEVIER\SEC29DET.DWG
DRAWN: K. ENGSTROM
JOB NO: U/534/AE-8
PLOT: STANDARD.PCP




EXHIBIT 'F' - RIG/FACILITIÉS LOCATION PLAT

# CHEVRON U.S.A. PRODUCTION COMPANY

# HYDROGEN SULFIDE CONTINGENCY PLAN SEVIER LAKE FEDERAL #1-29 MILLARD COUNTY, UTAH

# PURPOSE OF PROGRAM

It is Chevron U.S.A. Production Company practice to provide for the safety of its employees and contractor's employees at the job site, and to provide for the protection of the environment in accordance with applicable laws and regulations.

The primary purpose of this contingency plan is to guide location personnel in the responses expected of them in the event that hydrogen sulfide (H<sub>2</sub>S) is liberate during the drilling program.

Hydrogen Sulfide is extremely hazardous to normal oil field operations due to its capability (1) of destroying life at very low concentrations, and (2) of causing instantaneous failure of high strength metals. Drilling and producing operations of hydrocarbons containing toxic gases can, however, be performed safely and without incident when the necessary precautions are taken and the outlined safety procedures are followed. It is imperative that sulfide resistant materials be used, that the proper safety equipment be used, that this equipment be properly maintained, and that all safety regulations be complied with.

The procedures outlined are for your safety and the safety of all others; therefore, it is mandatory that each individual give his one hundred percent cooperation.

#### RESPONSIBILITIES AND DUTIES

#### **ALL PERSONNEL**

- 1. It is the responsibility of all personnel on location to familiarize themselves with the safety procedures.
- All personnel will attend to their personal safety first.
- 3. Help anyone who may be injured or overcome by toxic gases. The Drilling Representative will assign someone to administer first aid to unconscious person(s).
- Report to the designated "SAFE BRIEFING AREA" and follow the instructions of the Drilling Representative.

#### DRILLING REPRESENTATIVE

- It is the responsibility of the Drilling Representative to see that these safety and emergency procedures are observed by all personnel on location.
- The Drilling Representative will advise the Safety Specialist whenever the procedures as specified herein are complied with or cannot followed.
- The Drilling Representative will notify the Safety Specialist at least two weeks before the safety equipment specified herein is needed.
- 4. The Drilling Representative will keep the number of personnel on location to a minimum during hazardous operations.

- 5. The Drilling Representative is responsible for designating the "SAFE BRIEFING AREA". This "SAFE BRIEFING AREA" will change depending upon wind direction and must be redesignated as soon as a wind change occurs.
- 6. If an unexpected emergency occurs or the H<sub>2</sub>S alarm sounds, the Drilling Representative will assess the situation and will advise all personnel what condition exists.
- 7. When it is necessary to secure the location, the access road to location will be blocked, personnel from the rig crew will be used to guard same.


#### TEMPORARY SERVICE PERSONNEL

All service personnel, such as cementing crews, logging crews, specialists, mechanics, and welders will furnish their own safety equipment as required to comply with OSHA and the contrat requirements of Chevron U.S.A. Production Company.

## **VISITORS**

- 1. VISITORS will be restricted when Hydrogen Sulfide might be encountered, unless accompanied by the DRILLING REPRESENTATIVE for Chevron U.S.A. Production Company.
- Vistors and non-essential personnel will be prohibited from remaining in or entering contaminated areas where Hydrogen Sulfide concentration in the atmosphere exceeds 10 ppm.

NOTE: WHEN HYDROGEN SULFIDE MIGHT BE ENCOUNTERED, NO PERSONNEL ON LOCATION WILL BE PERMITTED TO SLEEP IN VEHICLES.




#### THE DRILL SITE

The location as shown in Figure 2 is planned in order to obtain the maximum safety benefits consistent with the rig configuration, well depth, and prevailing winds.

- 1. Through the use of several maps, the area within a two-mile radius of the location has been surveyed and contacts with all permanent residents haven been made. Except in a dead calm and a tremendous release of high concentration gases, the probability of lethal dosages beyond one mile is extremely unlikely. Note on the rig layout plat, Figure 2, the direction of the prevailing winds.
- 2. The location of houses, schools, roads, and anything where people may be present and who might need to be warned or evacuated in a crisis have been surveyed. This information with names and telephone numbers are keyed and listed on page 8 and Figure 3 for use if evacuation might be necessary should an emergency develop.
- 3. The drilling rig, see Figure 2, should be situated at such a location that prevailing winds blow across the rig toward the flare pit.
- 4. Two (2) SAFE BRIEFING AREAS will be established not less than 100 feet from the wellhead and in locations so that at least one SAFE BRIEFING AREA will be up-wind of the well at all times.
- 5. Protective equipment will be stored in strategic loations around the wellsite and each of the SAFE BRIEFING AREAS. Such equipment will include Self-Contained Breathing Apparatus (SCBA), First Aid Kits, Eye Wash Station, Stretchers, Hydrogen Sulfide Hand-Operated Detectors and Resuscitators. In the event of an emergency, personnel should assemble at the upwind SAFE BRIEFING AREA for instructions from their supervisor.
- 6. Windsocks or streamers will be utilized to give wind directions at several elevations; i.e., tree top, derrick floor level, and 6 to 8 feet above ground level. PERSONNEL SHOULD DEVELOP THE PRACTICE OF ROUTINE OBSERVATION OF WIND DIRECTION.
- 7. Windbreakers and rig curtains can be removed from around the derrick floor and monkey board, if hazardous amount of H<sub>2</sub>S are encountered.
- 8. Explosion proof ventilating fans (bug blowers) can be positioned to ensure adequate circulation at the derrick floor, cellar area and any other location where hydrogen sulfide is accumulating and needs to be dispersed.
- 9. When approaching a depth where Hydrogen Sulfide may be encountered, the MUD WILL BE MAINTAINED IN AN OVER-BALANCED CONDITOIN TO PRECLUDE THE ENTRY OF FORMATION FLUIDS INTO THE WELLBORE and thereby restrict the Hydrogen Sulfide to be treated to that contained in the formation drilled.
- 10. When approaching a depth where Hydrogen Sulfide may be encountered, appropriate warning signs will be posted.
- 11. When available, 24-hour radio or telephone communication will be provided at the rig. Emergency telephone numbers will be prominently posted: SHERIFF'S DEPARTMENT, AMBULANCE, HOSPITALS, DOCTORS, AND OPERATORS' SUPERVISORY PERSONNEL.


- 12. Filter-type gas masks are not suitable for use on drilling rigs. Pressure demand, SCBA's will be provided for use in any Hydrogen Sulfide concentration. They are not physically exhausting to use, are rugged and dependable, and require little maintenance.
- 13. SCBA's will be stored on racks and protected from the weather. Rig crew equipment will be located at a readily accessible location on the rig floor. For hygienic reasons, SCBA's are to be cleaned and sterilized at regular intervals. Employees working derricks will be equipped with a connection through a quick-disconnect from his system of breathing air so that if he must evacuate the derrick, he will have a full air bottle with his SCBA. A six-outlet air supply manifold will be installed on the rig floor for continuous use by crews and supervisory personnel working in a "masks-on" situation. The multi-bottle supply cylinder is to be located at approximately 150 feet from the well. A minimum of 3,600 cu. ft. of compressed breathing air will be on location at all times.
- 14. An alarm system which can be heard during operations and which can be activated from several points if gas is detected will be installed. When the alarm is sounded, personnel must assemble at the BRIEFING AREA.
- 15. There will be NO SMOKING on rig floor or near wellhead. Designated Smoking Areas will be provided by the Rig Supervisor.
- 16. Safety meetings and training sessions will be held at frequent intervals by the Safety Specialist, or the Drilling Representative. All persons required to work on location will be thoroughly familiar with the use, care and servicing of the following: Personal protective equipment, resuscitation equipment, and gas detection equipment.
- 17. All electric lighting, wiring, and electrical devices within 100 feet of the well will be put in vapor-proof condition to minimize the possibility of explosion.
- 18. Blowout preventers should meet or exceed the recommendations for hydrogen sulfide service (API RP 53). Choke manifolds will be of similar materials.
- 19. Inspection of installation, operation, and testing of blowout preventers, choke manifolds, etc., dressed for Hydrogen Sulfide services, will be conducted as required by Oil and Gas Order #6.
- 20. An accurate bottomhole location by use of single shot directional surveys will be maintained so that the well can be intercepted if it becomes necessary.
- 21. Every person involved in the operation will be informed of the characteristics of Hydrogen Sulfide and its dangers, safe procedures to use when it is encountered and recommended first aid procedures. This will be done through frequent safety talks and training sessions.
- 22. Personnel are required to have H<sub>2</sub>S/SCBA certification and must be clean shaven to provide a safe seal of the respiratory equipment.

# CHEVRON USA PRODUCTION COMPANY H<sub>2</sub>S Centingency Plan RIG LAYOUT Sevier Lake Federal #1-29



## RESIDENCES WITHIN TWO-MILE RADIUS OF SEVIER LAKE FEDERAL 1-29

Map Reference	Name of Resident	No. of Persons	Telephone
	None	0	n/a



#### NAMES AND DUTIES OF PERSONS WITH PRIME RESPONSIBILITIES

A. CHEVRON PRODUCTION COMPANY

(713) 754-2000

Name: D.A. Haddock

**Drilling Project Manager** 

**Business Phone:** 

(713) 754-5079

Name: TO BE SUPPLIED AT SPUD

**Drilling Representative** 

Name: TO BE SUPPLIED AT SPUD

**Drilling Representative** 

Name: TO BE SUPPLIED AT SPUD

**Drilling Representative** 

**Business Phone:** 

TO BE SUPPLIED AT SPUD

B. DRILLING CONTRACTOR

Name: TO BE SELECTED LATER

**Address: SUPPLIED LATER** 

Name/Title: TO BE SUPPLIED LATER

**Business Phone:** 

C. SAFETY CONTRACTOR

Name: TO BE SELECTED LATER

**Address: SUPPLIED LATER** 

Name/Title: TO BE SUPPLIED LATER

**Business Phone:** 

#### SEVIER LAKE FEDERAL

## **EMERGENCY TELEPHONE NUMBERS**

AMBULANCE	Delta	911
HOSPITAL	Delta Community Medical Ctr. Fillmore Community Medical	(801) 864-5591 (801) 743-5591
MEDICAL HELICOPTER	Salt Lake City-Life Flight	(801) 321-1234
LAW ENFORCEMENT	Millard County Sheriff Delta Fillmore	911 (801) 864-2755 (801) 743-5302
FIRE	Delta	911
CHEVRON SAFETY ENGINEER	Monty Hewett	(303) 675-3735
CHEVRON ENVIRONMENTAL SPECIALIST	Robin Smith	(713) 754-5046
BLM - OIL & GAS	Rex Rolle	(801) 743-6811
BURN CENTER	University of Utah - SLC	(801) 581-2340
POISON CONTROL	Salt Lake City	(800) 581-2340
NATIONAL RESPONSE CENTER	Oil & Toxic Chemical Spills	(800) 424-8802

#### PHYSICAL AND CHEMICAL PROPERTIES

#### OF HYDROGEN SULFIDE (HLS)

- 1. Extremely toxic (almost as toxic as Hydrogen Cyanide and 5 to 6 times as toxic as Carbon Monoxide).
- Coloriess.
- 3. Offensive odor, often described as that of rotten eggs.
- 4. Heavier than air specific gravity 1.189 (Air = 1.000 @ 60°F.). Vapors may travel considerable distance to a source of ignition and flash back.
- 5. Forms an explosive mixture with a concentration between 4.3 and 46 percent by volume with autoignition occurring at 500°F.
- 6. Burns with a blue flame and produces Sulfur Dioxide (SO<sub>2</sub>), which is less toxic than Hydrogen Sulfide but very irritating to eyes and lungs and causes serious injury.
- 7. Soluble in both water and liquid hydrocarbons.
- 8. Produces irritation to eyes, throat and respiratory system.
- 9. Threshold Limit Value (TLV) Maximum of eight hours exposure at 10 ppm.
- 10. Corrosive to all electrochemical series metals.
- 11. Boiling Point (-79°F).
- 12. Melting Point (-177°F).

#### PHYSICAL EFFECTS OF HYDROGEN SULFIDE POISONING

THE PRINCIPAL HAZARD IS DEATH BY INHALATION. When the amount of gas absorbed into the blood stream exceeds that which is readily oxidized, systemic poisoning results, with a general action on the nervous system. Labored respiration occurs shortly, and respiratory paralysis may follow immediately at concentrations of 700 ppm and above. This condition may be reached almost without warning as the originally detected odor of Hydrogen Sulfide may have disappeared due to olfactory paralysis. Death then occurs from asphyxiation unless the exposed person is removed immediately to fresh air and breathing stimulated by artificial respiration. Other levels of exposure may cause the following symptoms individually or in combinations:

- a. Headache
- b. Dizziness
- c. Excitement
- d. Nausea or gastro-intestinal disturbances
- e. Dryness and sensation of pain in nose, throat and chest
- f. Coughing
- g. Drowsiness

All personnel should be alerted to the fact that detection of Hydrogen Sulfide solely by smell is highly dangerous as the sense of smell is rapidly paralyzed by the gas.

#### H2S TOXICITY TABLE

1 ppm	= .0001%	(1/10,000 of 1%	s)Can smell
10 ppm	= .001%	(1/1000 of 1%)	Allowable for 8 hours' exposure. OVER THE ALLOWABLE CONCENTRATION, PROTECTIVE EQUIPMENT WILL BE NECESSARY.
100 ppm	= .01%	(1/100 of 1%)	Kills smell in 3 to 15 minutes. May burn eyes and throat.
200 ppm	= .02%	(2/100 of 1%)	Kills smell rapidly. Burns eyes and throat.
500 ppm	= .05%	(5/100 of 1%)	Looses sense of reasoning and balance. Respiratory disturbance in 2 to 15 minutes. Needs prompt artificial resuscitation.
700 ppm	= .07%	(7/100 of 1%)	Will become unconscious quickly. Breathing will stop and death result if not rescued promptly. Immediate artificial resuscitation.
1,000 ppm	= .10%	(1/10 of 1%)	Unconscious at once. PERMANENT BRAIN DAMAGE MAY RESULT UNLESS RESCUED PROMPTLY.

ppm = Parts of gas per million parts of air by volume.

1% = 10,000 ppm

### RESUSCITATION CHART

#### DID YOU KZOW?

# THERE IS NO TIME TO WASTE WHEN BREATHING STOPS!

## ARTIFICIAL RESUSCITATION MUST BE STARTED IMMEDIATELY!!!

After Breathing is Stopped for:	<u>The</u>	Chances	s for Life	аге	•
1 Minute	98	out of	100		
2 Minutes	92	out of	100		
3 Minutes	72	out of	100		
4 Minutes	50	out of	100		
5 Minutes	25	out of	100	*	
6 Minutes	11	out of	100	*	
7 Minutes	8	out of	100	*	
8 Minutes	5	out of	100	*	
9 Minutes	2	out of	100	*	
10 Minutes	1	out of	100	*	
11 Minutes	1	out of	1,000	*	
12 Minutes	1	out of	10,000	*	

<sup>\*</sup> Irreparable brain damage starts at about the fifth minute.

COOL-HEADED ACTION IN RESCUE IS CRITICAL

#### TREATMENT FOR HYDROGEN SULFIDE POISONING

#### INHALATION

As Hydrogen Sulfide in the blood oxidizes rapidly, symptoms of acute poisoning pass off when inhalation of the gas ceases. It is important, therefore, to get the victim of poisoning to fresh air as quickly as possible. He should be kept at rest and chilling should be prevented. If respiration is slow, labored, or impaired, artificial respiration may be necessary. Most persons overcome by Hydrogen Sulfide may be revived if artificial respiration is applied before the heart action ceases. Victims of poisoning should be under the care of a physician as soon as possible. Irritation due to sub-acute poisoning may lead to serious complications such as pneumonia. Under those conditions, treatment by the physician necessarily would be symptomatic. The patient should be kept in fresh air, and hygienic conditions should be watched carefully.

#### CONTACT WITH EYES

Eye contact with liquid and/or gas containing Hydrogen Sulfide will cause painful irritation (conjunctivitis). Keep patient in a darkened room, apply ice compresses to eyes, put ice on forehead, and send for a physician. Eye irritation caused by exposure to Hydrogen Sulfide requires treatment by a physician, preferably an eye specialist. The progress to recovery in these cases is usually good.

#### **CONTACT WITH SKIN**

Skin absorption is very low. Skin discoloration is possible after contact with liquids containing Hydrogen Sulfide. If such skin contact is suspected, the area should be thoroughly washed.

#### EFFECTS OF HYDROGEN SULFIDE ON METAL

Hydrogen Sulfide dissolves in water to form a weak acid that can cause some pitting, particularly in the presence of oxygen and/or carbon dioxide. However, the most significant action of H<sub>2</sub>S is its contribution to a form of hydrogen embrittlement known as sulfide stress cracking. Sulfide stress cracking is a result of metals being subjected to high stress levels in a corrosive environment where H<sub>2</sub>S is present. The metal will often fail catastrophically in a brittle manner. Sulfide stress cracking of steel is dependent upon and determined by:

- a. Strength (hardness) of the steel the higher the strength, the greater the susceptibility to sulfide stress cracking. Steels having yield strengths up to 95,000 psi and hardness up to Rc22 are generally resistant to sulfide stress cracking. These limitations can be extended slightly higher for properly quenched and tempered materials.
- b. Total member stress (load) the higher the stress level (load) the greater the susceptibility to sulfide stress cracking.
- c. Corrosive environment corrosive reactions, acids, bacterial action, thermal degradation, or low PH fluid environment.

Use as protection against sulfide stress cracking, all casing, BOP and safety equipment should be of H<sub>2</sub>S resistant material.

## CASING GRADES ACCEPTABLE FOR H2S SERVICE

CASING GRADE	H,S SERVICE	COMMENTS**
H-40	YES	••••
K-55	YES	••••
C-75	YES	
N-80	CONDITIONAL (Tempered)	ABOVE 200° F
L-80	YES	••••
MN-80	YES	••••
C-90	YES	••••
C-95	YES	••••
S-95	NO	ABOVE 200°F
S00-95	NO	ABOVE 200°F
SS-95	YES	ABOVE 200°F
S-105	NO	ABOVE 200°F
S00-90	YES	ABOVE 200°F
P-110	NO	ABOVE 200°F
S-135	NO	ABOVE 200°F
V-150	NO	ABOVE 200°F

<sup>\*</sup> Service conditions for any  $\rm H_2S$  environment.

<sup>\*\*</sup> Denotes usable grades above 200°F.

## DRILL PIPE GRADES FOR H2S SERVICE

GRADE	H,S SERVICE
D	YES
E	YES
X-95	YES
G-105	NO
S-135	NO
ALUMINUM	YES

#### DRILL STEM TEST

Open hole DST's will not be conducted in known  $H_2S$  intervals.

#### HLS SAFETY EQUIPMENT ON LOCATION

#### (PROVIDED BY SAFETY SPECIALIST)

- 1. Safety Trailer with a cascade system of 10-300 cu. ft. bottles of compressed breathing air complete with high pressure regulator, providing five men approximately 7 hours of breathing air.
- 2. Low Pressure Air Line (Approximately 1,000 feet depending on location). Equipped with quick connects.
- 3. One low pressure manifold system with six outlets.
- 4. Ten Scott Pressure Pac IIA, 30 minute pressure demand breathing apparatus NIOSH, MESA and USGS approved.
- 5. Six airline breathing apparatus c/w 7 cu. ft. egress cylinders.
- 6. Emergency Escape Unit (Robert Shaw) optional.
- 7. TAC H<sub>2</sub>S 3-Channel Monitor for multiple point continuous detection, each monitoring point is capable of activating remote audio and visual alarm system.
- 8. One Bendix Gastec, portable hand operated pump type detector with low and high range H<sub>2</sub>S detector tubes.
- 9. One OW2 Portable Oxygen Resuscitator.
- 10. One 24 Unit First Aid Kit.
- 11. One stretcher (Ferro Folding).
- 12. One Eye Wash Station.
- 13. Three Wind Socks with poles.
- 14. One High Pressure Compressed Air Refill Hose.
- 15. One H.S Condition Sign w/Flags.
- 16. One Fire Blanket.
- 17. One Light Explosion Proof.
- 18. One Siren Explosion Proof.
- 19. Traffic Cones as needed.
- 20. Two 300 cu. ft. bottles with Briefing Area Stand.

NOTE: MORE EQUIPMENT WILL BE ADDED IF WELL CONDITIONS REQUIRE.

#### IGNITING THE WELL

#### RESPONSIBILITY

THE DECISION TO IGNITE THE WELL IS THE RESPONSIBILITY OF THE DRILLING REPRESENTATIVE. In the event he is incapacitated, it becomes the responsibility of the Rig Tool Pusher. This decision should be made only as a last resort and in a situation where it is clear that:

- 1. Human life and property are endangered.
- 2. No hope exists for controlling the blowout under prevailing conditions at the well.

Notify the Denver ESF&H Staff, if time permits, but do not delay if human life is in danger. Initiate first phase of evacuation plan.

#### INSTRUCTIONS FOR IGNITING THE WELL

- 1. Two people are required for the actual igniting operation. They must wear self-contained breathing units and have a safety rope attached. One man will check the atmosphere for explosive gases with the Explosimeter. The other man is responsible for igniting the well.
- 2 Primary method to ignite: Meteortype Flare Gun.
- 3. Ignite upwind and do not approach any closer than is warranted.
- 4. Select the ignition site which is best for protection.
- 5. Select area for hasty retreat.
- 6. BEFORE FIRING, check regarding combustible gases.
- 7. Since Hydrogen Sulfide converts to Sulfur Dioxide, the area is not safe after igniting the well.
- 8. After igniting, continue emergency action and procedure as before.
- 9. All unassigned personnel will limit their actions to only those directed by the Drilling Representative.

REMEMBER: AFTER WELL IS IGNITED, HYDROGEN SULFIDE WILL CONVERT TO SULFUR DIOXIDE, WHICH IS ALSO HIGHLY TOXIC. DO NOT ASSUME THE AREA IS SAFE AFTER THE WELL IS IGNITED.

#### **BLOWOUT PREVENTION EQUIPMENT**

- 1. A kill line of ample strength and length will be laid to a safe point to allow pumping into the well in an emergency situation.
- 2. The closing unit should be located a safe distance from the wellbore and positioned for maximum utilization based on the prevailing wind direction.
- 3. BOP equipment will be tested as required by Onshore Order #2.
- 4. All equipment should be H<sub>2</sub>S trimmed for service in sour gas environments.

CONFIDENTIAL

#### SPECIAL EQUIPMENT

- 1. If a MUD-GAS SEPARATOR is installed, it will be installed with one or more flare lines.
- 2. Flare lines should be as long as practical and securely staked.
- 3. An automatic Hydrogen Sulfide monitor will be installed with a combination visual and audible alarm system located where it can be seen and or haerd throughout the drilling location. This system will have the capabilities of being activated from several points, which are the rig floor, cellar and shale shaker.
- 4. The automatic monitor should be set to trigger the drilling location visual/audible alarms when the Hydrogen Sulfide concentration in the atmosphere reaches 10 ppm. Explosion proof lights and sirens will be provided at or near the rig floor and such that all personnel will be subject to visual and audible warning.

#### MUD ADDITIVES

#### DRILLING FLUID RECOMMENDATION

#### **MUD TYPE**

The primary drilling fluid will be air. At the first indication of any concentration of  $H_2S$  gas will, the drilling fluid program will convert to an overbalanced mud with necessary additives for all stabilization.

In the event of H<sub>2</sub>S contamination of the mud system, Hydrogen Sulfide Scavengers should be added to the mud.

Quantities of zinc carbonate or ironite sponges can be stored on location should H<sub>2</sub>S neutralizer be necessary.

#### **EMERGENCY DRILLS**

#### Hydrogen Sulfide Alarm Drills

The Safety Specialist will conduct frequent H<sub>2</sub>S emergency drills for each crew by manually activating the H<sub>2</sub>S detector. When lights flash, all personnel on location will assemble at the Upwind Briefing Area. A head count will be taken at this time to determine if rescue operations are indicated. The Safety Specialist must be notified if more personnel are on location than during normal operations. A "Masks On" policy will prevail until the al clear is sounded. These drills will be implemented as frequently as required to familiarize all personnel with the procedures to be followed in the event an actual emergency occurs.

## A CLASS III CULTURAL RESOURCES INVENTORY FOR CHEVRON'S SEVIER LAKE FEDERAL 1-29 DRILL PAD AND ACCESS ROAD IN MILLARD COUNTY, UTAH (SECTION 29, T. 19 S, R. 10 W)

#### Prepared For:

U.S.D.I./Bureau of Land Management Warm Springs Resource Area Office 35 East 500 North P. O. Box 778 Fillmore, Utah 84631

Prepared Under Contract With:

Chevron U.S.A. Production Company Western Exploration Division P. O. Box 1635 Houston, Texas 77251

Prepared and Submitted By:

DESERT WEST RESEARCH, INC. P. O. Box 520427 Salt Lake City, Utah 84152-0427

13 February 1995

U.S.D.I./Bureau of Land Management Cultural Resources Use Permit No. 94UT55125

State of Utah Antiquities Survey Project No. U-95-WZ-047b

DESERT WEST RESEARCH TECHNICAL REPORT NO. 115

# COVER PAGE Must Accompany All Project Reports Submitted to Utah SHPO

Project Name: Sevier Lake Federal 1-29

State Proj. No.: U-95-WZ-047b

Report Date: February 1995

Principal Investigator: Kristopher R. Carambelas

Field Supervisor(s): Kristopher R. Carambelas

Acreage Surveyed

Intensive: 8.26 acres Recon/Intuitive: 0 acres

7.5' Series USGS Reference(s): Rocky Knoll, Utah

Sites Reported	Count	Smithsonian Site Numbers
Archaeological Sites		
Revisits (no inventory		
form update)	0	Not Applicable
Revisits (updated IMACS site	e	
inventory form attached)	0	Not Applicable
New Recordings (IMACS site		
inventory form attached)	0	Not Applicable
Total Count of Archaeological Site	es 0	Not Applicable
Historic Structures (USHS 106 Site form attached)	e info 0	Not Applicable
makal waterast make a men and a		
Total National Register Eligible S	Sites 0	Not Applicable

#### Checklist of Required Items

- X Copy of the Final Report.
- X Copy of 7.5' Series USGS Map with Surveyed/Excavated Area Clearly Identified.
- 3. \_\_\_ Completed IMACS Site Inventory Forms, Including
  - n.a. Parts A and B or C,
  - n.a. The IMACS Encoding Form,
  - n.a. Site Sketch Map
  - n.a. Photographs, and
  - n.a. Copy of the Appropriate 7.5' Series USGS Map w/the Site Location Clearly Marked and Labelled w/the Smithsonian Site Number.
- 4. n.a. Completed "Cover Sheet" Accompanying Final Report and Survey Materials.

gureau of Land Management Utah State Office			_				eport Acceptr Yes No itigation Accole Yes No
summary Report of Inspection for Cultural Resources (Form						C	omments:
1. Report Title	S E V	I E	R L	ΑK	E F	ED.	1 - 2 9       40
2. Development Company: (	Chevron U	I.S.A. Prod	uction Co.,	Western	Exploration	Division, H	· · · · · · · · · · · · · · · · · · ·
3. Report Date		1 3	Щ	1 9 9	5		4. Antiquities Permit No. : 94UT55125
5. Responsible Institution	D 47	ESE	RT	W E S	T R	E S .	County: Millard
6. Fieldwork Location  7. Resource Area W 5	TWN TWN  TWN  TWN  111	1 9 62 78 94	65 Rai	nge [	32	Section Section Section Section	70 71 72 73 74 75 76 77 (s) 86 87 88 89 90 91 92 93
PO=PONY EXPRESS, BR=BEAI HR=HOUSE RANGE, SE=SEVIE DA=KANAB, ES=ESCALANTE, S	R RIVER, I	HM=HENRY	MOUNTAIN	IS. BE=BE/	RINGS, BO=E	OOK CLIFFS	S, Fill in spaces 65, 69, 81, 85, 97, 101 only if: V=Vernal Meridian or H=Half Township
sum, inventory included a 60	0 x 600 ft.	area.					
9. Linear Miles Surveyed	ø	e	8	8	10	18	10. Inventory Type
and/or	112			<del></del>		117	R=reconnaisence, I=intensive, S=Statistical Sample 130
Definable Acres Surveyed and/or	۵	٥	Ø	æ	æ	8	
anaon	118					123	
*Legally Undefinable Acres	æ	ø	B	0	B	B	
Surveyed  (* A parcel hard to ca	124	oosto i o				129	
11. Description of Findings (a			center or s	ection	12. Nun	nber of Site	Found:No Sites=0 & & & & & & & & & & & & & & & & & & &
14. Actual/Potential National F	n/Date: As	sisted by A	Antiquities		off over the		

16. Conclusions/Recommendations: The proposec ertaking will have no effect on an within the 600 x 600 ft. project area.	y National Registgible properties. All activities should remain
17. Signature of Administrator & Field Supervisor:	Administrator XA.
*For extra locationals use additional 8100-3 Forms.	Field Supervisor [[ [ ]

#### I. ABSTRACT

Chevron U.S.A. Production Company intends to locate an exploratory well and access road in a portion of Section 29, T. 19 S, R. 10 W in Millard County, Utah. The well and access road are situated on lands administered by the Bureau of Land Management, Warm Springs Resource Area. Desert West Research, Inc. conducted a Class III cultural resources inventory of the proposed well pad and access road in February 1995 and found no cultural resources. Neither the well pad nor access road will affect any National Register eligible properties.

#### II. INTRODUCTION

The Western Exploration Division of Chevron U.S.A. Production Company (CPC) plans to locate an exploratory well and access road in Millard County, Utah. The proposed well and access road, hereafter referred to as Sevier Lake Federal 1-29, will be placed on lands administered by the Bureau of Land Management's (BLM) Warm Springs Resource Area. Desert West Research, Inc. (DWR), acting upon the request of Ms. Annette Bak of CPC, performed a Class III cultural resources inventory for Sevier Lake Federal 1-29 on February 13, 1995. The inventory was performed in compliance with Section 106 of the National Historic Preservation Act of 1966, as amended, as well as other rules and regulations that pertain to cultural resources (e.g. Executive Order 11593, The National Environmental Policy Act of 1969, and the Federal Land Policy and Management Act of 1976). The goals of the inventory were to: (a) identify and record cultural resources in the proposed project area; (b) provide information and recommendations regarding the significance and National Register eligibility of each resource; recommend whether the proposed undertaking would affect any National Register eligible properties; and (d) make recommendations for the treatment of National Register eligible properties relative to project objectives.

Field investigations were conducted by Kristopher Carambelas of DWR on February 13, 1995. Ground visibility was 100 percent and no problems were encountered in the field.

#### Description of the Project Area

Sevier Lake Federal 1-29 occupies a small (400 x 400 ft.) area just north of the northeastern shore of Sevier Lake and northwest of Bitterweed Lake (Figure 1). Access to the pad is from an exiting unimproved road, which is ca. 20 ft. south of the well pad's southern boundary. A sandy silt covers the project area and supports a moderate number of plant species typical of the shadscale community (i.e., Atriplex confertifolia and Sacrobatus baileyi). Cadastral descriptions for the project area include: SW/SE/NE 1/4 and SE/SE/NE 1/4 of Section 29 (T. 19 S, R. 10 W)

A number of cultural resources inventories have been conducted in the vicinity of Sevier Lake Federal 1-29 by DWR in the recent past (e.g., Carambelas 1994; Novak and Carambelas 1994), and Dr. Nancy Shearin, Warm Springs Resource Area Archaeologist, has directed investigations at an extremely large site (42Md1053) to the south for several years. However, none of these projects have explored the area encompassed by the drill pad. Since DWR's investigations in early 1994, no additional inventories have been conducted near the project area (E. Seelinger, Utah State Historic Office, Antiquities Section, personal communication 13 February 1995).

#### Field Methods

Prior to the inventory, land surveyors from Redcon (Bountiful, Utah) staked the project area with lath and flagging. One lath was placed in the center of the well pad and one lath was placed at each corner. One archaeologist walked parallel transects at 15 m intervals within the staked well pad; he also inventoried a 200 ft. buffer zone around the staked pad. In sum, a 600 x 600 ft. area (8.26 acres), which encompasses the access route to the pad, was examined.

#### III. INVENTORY RESULTS

As a result of the inventory, no cultural resources were located.

#### IV. EVALUATIONS & RECOMMENDATIONS

Archival and field examinations found no cultural resources in the proposed project area. As a consequence, the proposed undertaking will have no effect on any National Register eligible properties. To avoid affecting any unrecorded cultural resources, which may be near the well pad, all drilling activities and vehicles should remain within the area examined by the present inventory.

Note: The techniques used in this survey were such that most cultural resources existing in the project area visible to surface examination should have been found. If, however, additional cultural resources are discovered that could be adversely affected by project related activities, the latter should cease immediately and the Warm Springs Resource Area archaeologist should immediately be informed.

#### REFERENCES CITED

#### Carambelas, K. R.

1994 A Class III Cultural Resources Inventory for Chevron's Black Rock 2-D Seismic Program in Millard County, Utah: Line 1. Desert West Research Technical Report No. 103. Prepared for U.S.D.I./Bureau of Land Management, Warm Spring Resource Area, on behalf of Geophysical Systems Corporation, Pasadena, California. Report on file at Utah State Historic Preservation Office, Antiquities Section, Salt Lake City.

#### Novak, S. A. and K. R. Carambelas

A Class III Cultural Resources Inventory for Chevron's Black Rock 2-D Seismic Program in Millard County, Utah: Line No 3. Desert West Research Technical Report No. 104. Prepared for U.S.D.I./Bureau of Land Management, Warm Spring Resource Area, on behalf of Geophysical Systems Corporation, Pasadena, California. Report on file at Utah State Historic Preservation Office, Antiquities Section, Salt Lake City.




Figure 1. Location of Sevier Lake Federal 1-29 and Access Road (U-95-WZ-047b).

# UNITED PACIFIC INSURANCE COMPANY

HEAD OFFICE, FEDERAL WAY, WASHINGTON

RIDER

BOND NO. U89 75 81-34

To be attached to and form part of Bond Number U89 75 81-34 executed by CHEVRON CORPORATION AND ITS WHOLLY OWNED SUBSIDIARIES CHEVRON U.S.A. INC. AND CHEVRON EXPLORATION AND PRODUCTION SERVICES COMPANY, A DIVISION OF CHEVRON INDUSTRIES, INC., as Principal, and United Pacific Insurance Company, as Surety, in favor of the UNITED STATES OF AMERICA and dated July 18, 1976.

In consideration of the premium charged for the attached bond, it is hereby agreed that:

EFFECTIVE JULY 1, 1985 CHEVRON U.S.A. INC.
(A CALIFORNIA CORPORATION) WAS MERGED INTO
GULF OIL CORPORATION (A PENNSYLVANIA CORPORATION).
ALSO EFFECTIVE JULY 1, 1985, GULF OIL CORPORATION
CHANGED ITS NAME TO CHEVRON U.S.A. INC. (A
PENNSYLVANIA CORPORATION).

ALL OBLIGATIONS OF GULF OIL CORPORATION (A PENNSYLVANIA CORPORATION) UNDER FEDERAL INSURANCE COMPANY BOND NO. 8001-37-25 ARE ASSUMED BY CHEVRON U.S.A. INC. (A PENNSYLVANIA CORPORATION) UNDER THE BOND TO WHICH THIS RIDER ATTACHES.

The attached bond shall be subject to all its agreements, limitations and conditions except as herein expressly modified.

This rider shall become effective as of the 1st day of July, 1985.

Signed, sealed and dated this 26  CHEVRON CORPORATION  Principal	CHEVRON U.S.A. INC.  Principal
BY:	BY:
CHEVRON EXPLORATION AND PRODUCTION SERVICES COMPANY, A DIVISION OF CHEVRON INDUSTRIES, INC.  Principal	UNITED PACIFIC INSURANCE COMPANY Surety
BY:	BY: Helen A. Weires, Attorney-in-Fact

Med standing

Surety Bond No.: U 89 75 81 34
Bureau of Land Management Bond No.: ES0022

#### RIDER

In consideration for the payment of any additional premium charged for this rider and the acceptance of this rider by the Bureau of Land Management on behalf of the United States of America, the undersigned principal and surety hereby extend the coverage of Bon No. U 89 75 81 34, to all of the leases where the principal is the operator, whether or not the principal owns an interest in those leases. The principal hereby agrees to be bound by all terms and conditions of any lease wherein the principal is the operator until all the terms and conditions of the wherein the principal is the operator until all the terms and conditions of the lease have been satisfied, including the payment of any rentals and royalties due; provided, however, that this rider shall not act to increase the actual cumulative or potential liability of the surety above the face amount of the cumulative or potential liability of the surety above the face amount of the bond, one hundred fifty thousand and no/100 dollars (\$150,000.00); provided, bond, one hundred fifty thousand and no/100 dollars (\$150,000.00); provided, further, however, that any limitation of liability on the part of the surety shall not apply to the principal who shall be liable to the same extent as the lessees.

mes and Addresses of Witnesses	
	Chevron U.S.A. Inc.
	(Principal)
	By(Signature)
	(Title)
3Y:	United Pacific Insurance Company
Carol B. Henry Witness 580 California Street, Suite 1300	(Surety)
San Francisco, CA 94104	By(Signature)
	Shanon S. Dom -Attorney-in-Fact
	(Title)



# United States Department of the Interior



BUREAU OF LAND MANAGEMENT CALIFORNIA STATE OFFICE 2800 COTTAGE WAY, ROOM E-2845 SACRAMENTO, CALIFORNIA 95825-1889

CAS 019275A CAS 019275B 3104/3106 (CA-943.2b)

## OCT 18 1890 RECEIVED

# CERTIFIED -- RETURN RECEIPT REQUESTED

Tapo Energy Enterprises

# DECISION

OCI 2 9 1990
Property Administration
Lease Makharance/Western, Rocky
Hyombain, Michand

P.O. Box 41082
Bakersfield, CA 93384-1082
Decalta International Corporation
1801 Broadway, Suite 1500
Denver, CO 80202

Petrorep, Inc. 8580 Katy Freeway, Suite 310 Houston, TX 77024-1800

Middle Dome Corporation Attention: Land Department P.O. Box 11191 Bakersfield, CA 93389

Chevron U.S.A., Inc. P.O. Box 1635 Houston, TX 77251

United Pacific Insurance Company 4 Penn Center Plaza Philadelphia, PA 19103 oil and Gas

# Assignments Pending Approval Bond Requirements.

The records of this office show that the following oil and gas leases are committed to the Kettleman Hills Middle Dome Unit Agreement: CAS 019275A, CAS 019275B, CAS 019275C, CAS 019275D, CAS 019280A, and CAS 019280B. Middle Dome Corporation is the unit operator.

The record title interest in leases CAS 019275A and CAS 019275B is held by Decalta International Corporation (75%) and Petrorep, Inc. (25%). The record title interest in the remaining leases is held entirely by Chevron U.S.A. Inc.

Decalta International Corporation, as lessee, is furnishing bond coverage for pecarca incernacional corporacion, as lessee, is large punt coverage for leases CAS 019275A and CAS 019275B, and Chevron U.S.A. Inc., as lessee, 1s furnishing bond coverage for the remaining leases.

Assignments are pending approval which if approved will transfer 100% of the record title interest in leases CAS 019275A and CAS 019275B from Decalta International Corporation and Petrorep, Inc., to Tapo Energy Enterprises.

When the present holders of the above lease interests acquired these interests, bond coverage could be furnished by one of the following three methods:

- The lessees could furnish the bond coverage.
- A holder (owner) of operating rights could furnish the bond coverage.
- The unit operator for the unit agreement could furnish the bond 2.

The bond regulations have just recently changed. The present regulations require the operator on the ground to have bond coverage in one of the following ways:

- Furnish an oil and gas lease bond (Form 3000-4, June 1988 edition) on which he is the principal.
- 2.
- Permission to use a lessee's bond: If a surety bond, permission is granted by bond rider executed by the surety. a.
  - If a personal bond, permission is granted by the principal (obligor) on the personal bond. Ъ.
  - Permission to use a sublessee's bond: 3.
    - If a surety bond, permission is granted by bond rider executed by the surety. a.
    - If a personal bond, permission is granted by the principal (obligor) on the personal bond. Ъ.
    - Furnish a collective corporate surety bond as described in 43 CFR 3186.2 on which he is the principal. This type of bond requires the on the ground operator to be a unit operator.

At the time the present lessees obtained these lease interests, the lease records indicate both Decalta International Corporation and Petrorep, Inc., had nationwide oil and das lease bonds. At the present time this office is unable to find any bond for Petrorep, Inc. It cannot be detrained from the lease records whether they are in error as to the filing of a bond for Petrorep. Inc., or the bond was inadvertently released at a later date. In any event, this office considered Petrorep, Inc., responsible for furnishing bond coverage under the bond procedures in effect when they acquired their interest in the leases.

For the leases and unit agreement here in question, Chevron U.S.A. Inc. is the operator on the ground.

Chevron U.S.A. Inc. maintains a \$150,000.00 nationwide oil and gas bond, for which United Pacific Insurance Company is the surety. The bond is identified by the Bureau of Land Management's bond which United Pacific Insurance Company is the Bureau of Land Management's bond which United Pacific Insurance Company is the Bureau of Land Management's bond the surety's bond No. U 89 75 81 34 and by the Bureau of Land Management's bond the surety's bond is on an old bond form which does not have a provision for No. ES0022. This bond is on an old bond form which does not have a provision is in the current bond coverage when the principal is the operator for a lease or leases, however, this provision is in the current no interest in the lease or leases, however, this provision is in the current bond form.

If Chevron U.S.A. Inc. and United Pacific Insurance Company will execute and return to this office the bond rider enclosed with Chevron U.S.A. Inc.'s copy of return to this office the bond rider enclosed to include the provision for this decision, bond U 89 75 81 34 will be amended to include the principal is this decision, bond U 89 75 81 34 will be amended to include the principal is the principal to be covered by the bond in those instances when the principal is the principal to be covered by the bond in those instances when the lease or leases.

If the rider is executed and filed with this office, the assignments pending approval may be approved. However, if the parties involved do not wish to approval may be approved in lieu of the rider may be provided by any of provide the rider, bond coverage in lieu of the rider may be provided by any of the rider, bond coverage in lieu of the rider may be provided by the regulations. If another method is going to be the other methods allowed by the regulations. If another method forms and the other methods allowed by the regulations the appropriate bond forms and used, this office must be notified so that the appropriate bond forms and instructions may be furnished to the applicable party.

Fred O'Ferrall
Chief, Leasable Minerals Section

Enclosure as stated

CERTIFIED--RETURN RECEIPT REQUESTED

Chevron U.S.A. Inc.

P.O. Box 5050

San Ramon, CA 94583-09050

To be attached to and form part of Bond Number U89 75 81-34 executed by CHEVRON CORPORATION AND ITS WHOLLY OWNED SUBSIDIARIES, CHEVRON U.S.A. INC. AND CHEVRON INDUSTRIES, INC., Principals, and UNITED PACIFIC INSURANCE COMPANY, as Surety. in favor of THE UNITED STATES OF AMERICA and dated July 18, 1976.

In consideration of the premium charged for the attached bond, it is hereby agreed that:

Effective July 1, 1985, Chevron U.S.A. Inc.(A California Corporation) was merged into Gulf Oil Corporation (A Pennsylvania Corporation). Also effective July 1, 1985, Gulf Oil Corporation changed its name to Chevron U.S.A. Inc.(A Pennsylvania Corporation).

All obligations of The Pittsburg & Midway Coal Mining Company, formerly a Subsidiary of Gulf Oil Corporation, now a Subsidiary of Chevron Corporation, under Federal Insurance Company Bond number 8083-70-29 are assumed by the United Pacific Insurance Company Bond to which this rider attaches.

The attached bond shall be subject to all its agreements, limitations and conditions except as herein expressly modified.

This rider shall become effective as of the 1st day of July, 1989.

Signed, sealed and dated this	30th day of <u>June</u> , 1989.
Name and Address of Witnesses	Name and Address of Principal(s) and Surety
	CHEVRON CORPORATION Principal
	BY:
	CHEVRON U.S.A. INC. Prinicpal
	BY:
	CHEVRON INDUSTRIES, INC.
	Principal
	BY:
	UNITED PACIFIC INSURANCE COMPANY Surety
Marsh & McLennan, Inc. Three Embarcadero Center San Francisco, CA 94111	BY:  Helen A. Weires, Attorney-in-Fact 580 California Street, Suite 1300 San Francisco, CA 94104

CONFIDENTAL

To be attached to and form part of Bond Number U89 75 81-34 executed by CHEVRON CORPORATION AND ITS WHOLLY OWNED SUBSIDIARIES, CHEVRON U.S.A. INC. AND CHEVRON INDUSTRIES, INC., Principals, and UNITED PACIFIC INSURANCE COMPANY, as Surety, in favor of THE UNITED STATES OF AMERICA and dated July 18, 1976.

In consideration of the premium charged for the attached bond, it is hereby agreed that:

Effective July 1, 1985, Chevron U.S.A. Inc. (A California Corporation) was merged into Gulf Oil Corporation (A Pennsylvania Corporation). Also effective July 1, 1985, Gulf Oil Corporation changed its name to Chevron U.S.A. Inc. (A Pennsylvania Corporation).

All obligations of Gulf Oil Corporation under Federal Insurance Company Bond Numbers 8001-37-25 and 8036-41-78 are assumed by the United Pacific Insurance Company Bond to which this rider attaches.

The attached bond shall be subject to all its agreements, limitations and conditions except as herein expressly modified.

This rider shall become effective as of the 1st day of July, 1989.

	Signed	sealed	and dated	this30	th day of June, 1989.
Name	and Add	iress of	Witnesses		Name and Address of Principal(s) and Surety
					CHEVRON CORPORATION
					Principal
					ВҮ:
					CHEVRON U.S.A. INC.
	<del></del>		<del> </del>		Principal
					BY:
					CHEVRON INDUSTRIES, INC.
					Principal
					ВҮ:
					UNITED PACIFIC INSURANCE COMPANY
				<u> </u>	Surety
					BY:
Thre	e Embar	ennan, l cadero (	Center		Helen A. Weires, Attorney-in-Fact 580 California Street, Suite 1300 San Francisco, CA 94104



RELIANCE I: RANCE COMPANY PHILADELPH 'NSYLVANIA

UNITED PACIFIC INSURANCE COMPANY FEDERAL WAY, WASHINGTON

PLANET INSURANCE COMPANY FEDERAL WAY, WASHINGTON

R	IDER						
Τ	o be attached to and form a part of						
Type of Bond: _	State or Nationwide oil and Gas bond						
O d No.	Chevron Corporation and its wholly send substitution, Chevron C.E.A. Inc. and Chevron George Company, A Division of Chevron Industries,, as Principal,						
executed by	inc.						
and by _	Entree Pholine INSURANCE COMPANY, as Surety,						
in favor of _	Control of the Contro						
	5015 le, 1976						
4110 00.00	n consideration of the premium charged for the attached bond, it is hereby agreed to change:						
•	and the annual of the pro-						
From:	Chesto Corporation and it whose owner cutation live, whose cutation live.						
From.	and Checker, Guescience Company, a Dividie, or Checken Foundation, Inc.						
	Chevron Corporation and its wholly owned submidiaries, Chevron bross, inc.						
To:							
	was chester anductores, I have						
	The attached bond shall be subject to all its agreements, limitations and conditions except as herein expressly modified.						
This rider is effective	de, wilder 1, at attention						
Signed and Sealed	and a contract of the contract						
Principa	Contraction Comments and Contraction Contr						
Ву							
-,	INSURANCE COMPANY						

CONFIDENTIAL

By:

Date

Attorney-in-Fact

RIDER ACCEPTED (Please sign duplicate of this Rider and return to Surety)

#### RIDER TO EXTEND COVERAGE OF NATIONWIDE BOND TO UNIT AGREEMENT AND PERMIT TERMINATION OF PRIOR BOND

BLM Bond No.: ES-0022

Surety Bond No.: U89 75 81 34

It is hereby agreed by and between the undersigned principal and surety in consideration for any additional premium charged for this rider, its acceptance by the Bureau of Land Management (BLM) on behalf of the United States, and the termination of the period of liability by the BLM on behalf of the United States on Bond No. 0794-96-52 carrying Chevron U.S.A. Inc. (formerly Gulf Oil Corp.) as principal, and Federal Insurance Company as surety, that the coverage of this bond is extended to any and all liabilities that may be outstanding on Bond No. 0794-96-52.

The undersigned principal and surety also agree to extend coverage of this bond to include all obligations of the principal under the South Canyon Unit Agreement No. 14-08-001-2089 and all the obligations of the Federal oil and gas leases committed to such unit agreement. The pricipal and surety agree to remain bound for the failure to comply with any terms and condition of the unit agreement and leases now or hereafter committed thereto; including, but not limited to, the payment of rentals and royalties and the obligation to plug and abandon properly all wells drilled on such leases under the unit agreement.

Provided, that termination or contraction of the unit agreement shall not cause any diminution of the principal's or surety's obligation with respect to lease obligations incurred during the existence of such unit agreement; and provided, that the rider shall not increase the cumulative or potential liability of the surety above the face amount of the bond, to wit one hundred fifty thousand dollars (\$150,000.00); and provided, that any such limitation on the part of the surety shall not apply to the principal's obligations to comply with the terms and conditions of all leases committed to the unit agreement, either presently or hereafter.

to the mult agreement, eremet because	
Executed thel2th day of	April , 19 89 . CHEVRON CORPORATION
Witness and Address	Principal
Witness and Address	UNITED PACIFIC INSURANCE COMPANY Surety
Starline Amillo Witness and Address	Surety's Agent Attorney-in-Fact
Marsh & McLennan, Inc.	

Three Embarcadero Center San Francisco, CA 94111 CONTIDITION

Rider to Bond No. U89 75 81-34 (Continued)

Witness and Address

	CHEVRON U.S.A. INC. Principal
Witness and Address	ВУ
Withess and manager	CHEVRON EXPLORATION AND PRODUCTION SERVICES COMPANY, A DIVISION OF CHEVRON INDUSTRIES, INC.  Principal
	ВУ

CONTIDICATAL

SEP 16, '93 08:06 I , TIFIC INBURAN E OFFICE, TACOMA, WASHINGTON POWER OF ATTORNEY KNOW ALL MCN BY THESE PRESENTS, That the UNITED PACIFIC INSURANCE COMPANY, a corporation duly organized under the laws of the State of Washington, does hereby make, constitute and appoint C. MICHAEL HENLEY Of LOS ANGELES, CALIFORNIA----its true and lawful Attorney-in-fact, to make execute, seal and deliver for and on its behalf, and as its act and deed ANY AND ALL BONDS AND UNDERTAKINGS OF SURETYSHIP---and to bind the UNITED PACIFIC INSURANCE COMPANY thereby as fully and to the same extent as if such bonds and undertakings and other writings obligatory in the nature thereof were signed by an Executive Officer of the UNITED PACIFIC INSURANCE COMPANY and seeled and attested by one other of such officers, and hereby ratifles and confirms all that its said Attorney(s) in: fact may do in pursuence hereof. This Power of Attorney is granted under and by authority of Section 37A of the By-Laws of UNITED PACIFIC INSURANCE COMPANY which provisions are now in full force and effect, reading as follows: RECTION 1. The Board of Directors, the President, or any Vice-President or Assistant Vice-President shall have power and authority to: (a) appoint SECTION 37A - ATTORNEYS-IN-FACT RESISTION TO THE BOARD OF DIRECTORS, THE FRESHORMS, OF any VICE-FRESHORMS OF ASSISTENT VICE-FRESHORMS SHELL DIRECTORS, CONTINCES OF INCEMENTS AND OTHER AND THE BOARD OF THE COMPANY OF THE BOARD OF THE COMPANY OF THE BOARD OF THE COMPANY OF THE BOARD OF witings obligatory in the nature thereof, and (b) to remove any such Attorney-In-fact at any time and revoke the power and authority given to him. RECTION 2. Attorneys-in-fact shall have power and authority, subject to the terms and limitations of the power of attorney issued to them, to execute ALCITION IN ALTOTREYS IN THE STALL HAVE POWER AND ALL HOUSE TO THE TERMS AND HIMILETINES OF THE POWER OF ALTOTREYS IN THE HOUSE TO ENGLISHED THE TERMS OF THE POWER OF ALTOTREYS IN THE HOUSE THE TERMS OF THE COLLOCATE SEAL IS NOT RECOGNIZED TO THE VALUE OF THE VALUE OF THE POWER This power of attorney is signed and sealed by fectimile under and by authority of the following Resolution adopted by the Board of Directors of Util TED PACIFIC INSUITANCE COMPANY at a meeting held on the 28th day of October, 1871, at which a quorum was present, and seld Resolution the nature thereof. "Resolved, that the signatures of such directors and officers and the seal of the Company may be affixed to any such power of has not been amended or repealed: mesolved, that the signatures of such directors and officers and the seal of the Company may be astrict to any such power of attorney or any certificate relating thereto by facsimile, and any such power of attorney or certificate bearing such facsimile signatures or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by facsimile signatures and facsimile seal shall be valid and binding upon the Company in the future with respect to any bond or transfer to which is in accordant. IN WITNESS WHEREOF, the UNITED PACIFIC INSURANCE COMPANY has caused these presents to be signed by its Vice-President, and its corporate undertaking to which it is attached." 10.75 UNITED FACIFIC INSURANCE COMPANY March 18thy of wel to be hereto effixed, this\_ SEAL Executive Washington STATE OF Pierce BROWN MORRIS E. to me known to be the Vite Platition of the UNITED PACIFIC INSUHANCE COMPANY, and . 19.75 personally appeared. March 18th\_day of acknowledged that he executed and attested the foregoing instrument and affixed the seal of said corporation thereto, and that Section 37A, Section 1 1u

On this. and 2 of the By Laws of said Company and the Resolution, set forth therein, are still in full force. My Commission Expires: Notary Public in and for State of Washington January 15 Residing at Tacoma D. Keith Johnson . Assistant Secretary of the UNITED PACIFIC INSURANCE COMPANY, do hereby certify that the bove and foregoing it a true and correct copy of a Power of Attorney executed by said UNITED PACIFIC INSURANCE COMPANY, which is still in full

IN WITHESS WHEREOF, I have hereunto set my hand and affixed the seal of said Company this,

W8DU-1431 ED. 6/74

force and effect.

# CONFIDENTIAL

oem 1120–20 optember 1966) (Intmosty 4-1187)

#### UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

U 89 75 81 - 94 Bond No:

STATE OR NATIONWIDE OIL AND GAS BOND Act of February 23, 1920 (30 U.S.C. Sec. 181); Act of August 7, 1947 (30 U.S.C. Sec. 351)

Standard Oil Company of California and NOW ALL MEN BY THESE PRESENTS, That we Cherron Oll Company its wholly-owned Subsidiary,

225 Bush Street; Sen Francisco, California in principal, and United Pacific Insurance Company

1 Market Plane: San Francisco California in the sum of surety, are held and firmly bound unto the United States of America in the sum of One hundred fifty thous 000.00 ), lawful money thousand ... dollars (\$150,000,00 I the United States, which sum may be increased or decreased by a rider hereto executed in the same manner as this and no/100and, for the use and benefit of (1) the United States; (2) the owner of any of the land subject to the coverage of this mind, who has a statutory right to compensation in connection with a reservation of the oil and gas deposits to the "inited States; and (3) any lessee or permittee under a lease or permit issued by the United States prior to the issuore of an oil and gas lease for the same land subject to this bond, covering the use of the surface or the prospecting or, or development of, other mineral deposits in any portion of such land, to be paid to the United States. For such "yment, well and truly to be made, we bind ourselves, and each of our heirs, executors, administrators, successors nd assigns, jointly and severally.

If the amount of this bond is \$150,000 or if it is increased to that amount, the coverage shall extend to all of the prin-Ipal's holdings of federal oil and gas leases in the United States, including Alaska, under the Acts cited in Schedile A.

If the amount of this bond is less than \$150,000, its coverage extends only to the principal's holdings of federal oil and gas leases in the States named in Schedule A and to any other State or States that may be named in a rider atniched hereto by the lessor with the consent of the surety.

#### SCHEDULE A

Public Domain Leasing Act of February 25, 1920 (30 U.S.C. Sec. 181)

NAMES OF STATES

Acquired Lands Lessing Act of August 7, 1947 (30 U.S.C. Sec. 351)

NAMES OF STATES

	Post-It brand fex transmittal memo 7671 set pages > 5  To Annextee Bak From Co.  Co.  Phone 1944 - 0338  Phone 1943 - 2854
conditions of the foregoing obligations are such to whereas the said principal has an interest in oil	WHEREAS the principal and surety agree that without notice to the surety the coverage of this bond, in addition to the present holdings of the principal, shall

The and gas leases issued under the Act or Acts cited in Schedule A of this bond: (1) as lesses; (2) as the approved holder of operating rights in all or part of the lands covered by such leasus under operating agreements with the lessows; or (3) as designated operator . agent under such issues pending approval of an arraignment or operating agreement; and

WHEREAR the principal is authorized to drill for, mine, extract, remove, and dispose of oil and gas deposits in or under the lands covered by the leases, operating agreements or designations and is obligated to comply with certain covenants and agreements set forth in such instruments; and

tion to extend to and include:

- 1. Any oil and gas lease hereafter issued to, or scquired by the principal in the States now named in Schedule A, or later named in a rider, the coverage to be confined to the principal's holdings under the Act or Acts cited at the head of the column in which the name of the State appears and to become effective immediately upon such issuance or upon departmental approval of a transfor in favor of the principal.
- 2. Any operating agreement hereafter entered into or acquired by the principal affecting oil and gas leases in the States now named in Schedule A, or later named in a rider. The coverage shall become

said athms of the काक्तरावत ।समात्र्यायात्रोते कील्म सृत्यः agreement or of a transfer of an operating agreement to

the principal. 3. Any designation subsequent bereto of the principal as operator or agent of a lessee under a lease issued pursuant to the Act or Acts cited in Schedule A and covering lands in a State named in Schedule A, either presently or by rider. This coverage shall become effective immediately upon the filing of such a designation under a lease.

4. Any extension of a lease covered by this bond, such coverage to continue without any interruption due to the expiration of the term set forth in the lease.

Provided, that the surely may elect to have the additional coverage authorized under this paragraph become inapplicable as to all interests of the principal acquired more than thirty (30) days after the receipt of notice of such election by the Bureau of Land Management.

The surety hereby waives any right to notice of, and agrees that this bond shall remain in full force and effect notwithstanding:

- 1. A transfer or transfers, either in whole or in part, of any or all of the leases, or of the operating agreements, and further agrees to remain bound under this bond as to the interests either in the lesses of in the operating agreements, or in both, retained by the principal when the approval of the transfer or transfers become effective.
- 2. Any modification of a lease or operating agreement, or obligations thereunder, whether made or effected by commitment of such lease or operating agreement to unit, cooperative, communitization or storage, agreeor development contracts, suspensions of operamer tia in to

of and sainly besely agree that notwithstanding . Terminution of any lease or busses. HILDREAD ING ... operating agreements or designations as operator or agent, covered by this bond, whether the termination is by operation of law or otherwise, the bond shull remain in full force and effect as to all remaining leases, operating agreements, or designations covered by the bond; and

WHEREAS the principal, as to any leave or part of u lease for lands as to which he has been designated asoperator or agent, or approved as operator, in consid eration of being permitted to furnish this bond in lieu of the lessees, agrees and by these presents does hereby bind himself to fulfill on behalf of each lessee all obligations of each such lease for the entire lease hold in the same manner and to the same extent as though he were the lessee; and

WHEREAS the principal and aurety agree that the neg lect or forbestance of said lessor in enforcing. against the lessess of such lessor, the payment of rentals or royalties or the performance of any other covenant, condition or agreement of the leases, shall not, in any way, release the principal and surely, o. either of them, from any liability under this bond; and

WHEREAS the principal and surety agree that in the event of any default under the leases, the lessor mu) commence and prosecute any claim, suit, action, or other proceeding against the principal and surely, or either of them, without the necessity of joining the lessees.

NOW, THEREPORE, IF said principal shall in wit respects faithfully comply with all of the provisions of

ments, or development contracts, suspensions of opera- ments, or development contracts, suspensions or changes tions or production, waivers, suspensions or changes in rental, minimum royalty and royalties, compensatory royalty payments, or otherwise; and	the leases referred to heminbofom, then the above obligations are to be void; otherwise to remain in full force and effect.
Signed on this 24thday of June The effective date of this bond is July 18th	Ce / Mulli
K. H. BOERO 225 Bush Street, San Francisco, CA 94104 NAMES AND ADDRESSES OF WITNESSES	BY:
Lynnan	CHEVRON OIL COMPANY  WILL CONTINUE OF SELECTION (L. B.  (L. B.
225 Bush Street, San Francisco, CA 94104	
	225 Bush Street; San Francisco, Califor
	UNITED PACIFIC INSURANCE COMPANY

San Francisco, California EMECUPACION OCCUPARTS

1 Market Plass

That Place

Ban Francisco, California

1 Market Plaza; San Francisco, Californ

EURIUE

ATTORNEY IN PACT

(Business address)

JME OFFICE, TACOMA, WASHINGTON

## OWER OF ATTORNEY

KNOW ALL MEN BY THESE PRESENTS. That the UNITED PACIFIC INSURANCE COMPANY, a corporation duly organized under the laws of the State of Washington, does hereby make, constitute and appoint

C. MICHAEL HENLEY of LOS ANGELES, CALIFORNIA----

its true and lawful Attorney-in-fact, to make execute, seel and deliver for end on its behalf, and as its act and deed

ANY AND ALL BONDS AND UNDERTAKINGS OF SURETYSHIP----

and to hind the UNITED PACIFIC INSURANCE COMPANY thereby as fully and to the same extent as if such bonds and undertakings and other writings obligatory in the nature thereof were signed by an Executive Officer of the UNITED PACIFIC INSURANCE COMPANY and sealed and attested by one other of such officers, and hereby ratifies and confirms all that its said Attorney(s)-in-fact may do in pursuence hereof.

This Power of Attorney is granted under and by authority of Section 37A of the By-Laws of UNITED PACIFIC INSURANCE COMPANY which provisions are now in full force and effect, reading as follows:

## SECTION 37A - ATTORNEYS-IN-FACT

RECTION 1. The Brand of Directors, the President, or any Vice-President or Assistant Vice-President shall have power and authority to: (a) eppoint Atturneys-in-fact and to authorize them to execute on behalf of the Company, bonds and undertakings, recognizances, contracts of Indemnity and other witings obligatory in the nature thereof, and (b) to ramove any such Attorney-In-fact at any time and revoke the power and authority given to him.

RECTION 2. Attorneys-in-fact shall have power and authority, subject to the terms and limitations of the power of attorney issued to them, to execute and deliver on behalf of the Company, bonds and undertakings, recognizances, contracts of indemnity and other writings obligatory in the nature thereof. The corporate seal is not necessary for the velidity of any bonds and undertakings, recognizances, contracts of indemnity and other writings obligatory in the nature thereal.

This power of attorney is signed and sealed by feccimile under and by authority of the following Resolution adopted by the Board of Directors of UHITED PACIFIC INSURANCE COMPANY at a meeting held on the 28th day of October, 1971, at which a quorum was present, and seld Resolution has not been arranded or repealed:

"Resolved, that the signatures of such directors and officers and the seal of the Company may be affixed to any such power of nestrived, that the signatures or such directors and distincts and the sest of the Company may be attixed to any such power of attorney or any certificate relating thereto by facsimile, and any such power of attorney or certificate bearing such facsimile signatures or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by facsimile signatures and facsimile seal shall be valid and binding upon the Company in the future with respect to any bond or facsimile signatures and facsimile seal shall be valid and binding upon the Company in the future with respect to any bond or facsimile seal shall be valid and binding upon the Company in the future with respect to any bond or

undertaking to which it is attached." IN WITNESS WHEREOF, the UNITED PACIFIC INSURANCE COMPANY has caused these presents to be signed by its Vice-President, and its corporate 18thy of March UNITED PACIFIC INSURANCE COMPANY wal to be hereto affixed, this\_ Executive Washington STATE OF Washingto MORRIS E. BROWN March 19.75 personally appeared\_ , to me known to be the Vice President of the UNITED PACIFIC INSUHANCE COMPANY, and 18th day of. acknowledged that he executed and attested the foregoing instrument and affixed the seal of said corporation thereto, and that Section 37A, Section 1 and 2 of the By-Laws of said Company and the Resolution, set forth therein, are still in full force, My Commission Expires: Notary Public in and for State of Washington January 15 . 19 . 78 Residing et Tacoma

D. Keith Johnson . Assistant Secretary of the UNITED PACIFIC INSURANCE COMPANY, do hereby certify that the shows and foregoing it a true and correct copy of a Power of Attorney executed by said UNITED PACIFIC INSURANCE COMPANY, which is still in full force and allact.

IN WITNESS WHEREOF, I have hersunto set my hand and affixed the seal of said Company this...

WEDU-1431 ED. 6/74

"ACIFIC INSURANCE C UNIT a. HUM SUFFICE, TACOMA, WASHINGTO.

CHANGE OF NAME RIDER

To be attached to and form part of Bond Number

U89 75 81 34

executed by

STANDARD OIL COMPANY OF CALIFORNIA AND ITS WHOLLY OWNED SUBSIDIARY, CHEVRON OIL COMPANY

as Principal, and UNITED PACIFIC INSURANCE COMPANY, as Surety, in favor of UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

tem visitant spice, thee, 30, 1977

State or Nationwide oil and gas bond . 1976. and dated July 18 It is hereby agreed that the name of the Principal is changed to: STANDARD OIL COMPANY OF CALIFORNIA and its wholly owned subsidiary, CHEVRON U.S.A. Inc. Provided, however, that the liability of the Surety under the attached bond and under the attached bond as changed by this rider shall not be cumulative. The attaches bond shall be subject to all its agreements, limitations and conditions except as herein expressly modified. , 1977, standard time. January day of This rider shall become effective as of the 1st day of November , 1976. 30th Signed, sealed and dated this CHEVRON OIL COMPANY Principal For your information - Chevron Oil Company will change its name to CHEVRON U.S.A. Inc. effective ASSISTANT SECRETARY January 1, 1977. 6. MICHAEL HENLEY, ATTORNEY-IN-Oblines State of California County of Los Angeles . 19 76 , before me, the undersigned, a Notary Public in and for said County. known to me to be the person whose name is November 23rd personally superiod \_ C. Michael Henley subscribed to the within instrument as Attorney-In-Fact of UNITED PACIFIC INSURANCE COMPANY, and acknowledged to me that \_\_\_\_ he subscribed the name of UNITED PACIFIC INSURANCE COMPANY, as Surety, and h is own name as Attorney in Fact CIFFICIAL SUAL

RITH E. LE DUG

NOTABY PUBLIC CALIFORNIA

Charlet of CIFFICIAL SUAL


AND ADD TO SUBJECT OF THE SUAL

AND THE SU

## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/23/95	API NO. ASSIGNED: 43-027-30035
WELL NAME: SEVIER LAKE FEDERAL 1-2 OPERATOR: CHEVRON U.S.A. INC (N	
PROPOSED LOCATION: SENE 29 - T19S - R10W	INSPECT LOCATION BY: / /
SURFACE: 2250-FNL-0700-FEL BOTTOM: 2250-FNL-0700-FEL	TECH REVIEW Initials Date
MILLARD COUNTY WILDCAT FIELD (001)	Engineering
LEASE TYPE: FED	Geology
LEASE NUMBER: UTU - 72587	Surface
PROPOSED PRODUCING FORMATION: PRCA	M.
RECEIVED AND/OR REVIEWED:	LOCATION AND SITING:
<pre>Plat Bond: Federal[Y State[] Fee[]</pre>	R649-2-3. Unit:
(Number <u>(189-75-18/-34</u> ) <u>M</u> Potash (Y/N)	R649-3-2. General.  R649-3-3. Exception.
✓ Oil shale (Y/N) ✓ Water permit	Drilling Unit.
(Number Locat WATER WILL)  N RDCC Review (Y/N)	Board Cause no:
(Date:)	Date:
COMMENTS: Exception Req	UEST RECEIVED
STIPULATIONS:	

CHEVRON U.S.A. PRODUCTION SEVIER LAKE FEDERAL 1-29 WILDCAT SEC. 29, T 19 S, R 10 W MILLARD COUNTY, NO SPACING






DATE: 03/24/95

April 27, 1995

Chevron Chevron

SEVIER LAKE FEDERAL 1-29 USA UTU-72587 SE4NE4 SECTION 29-T19S-R10W 2250' FNL, 700' FEL MILLARD COUNTY, UTAH



Chevron U.S.A. Production Company Western Exploration Division P.O. Box 1635 Houston, TX 77251

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
355 W. North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

ATTENTION: Mr. Mike Hebertson

#### Gentlemen:

Pursuant to State of Utah R649-3-3 <u>Exception to Location and Siting of Wells</u>, Chevron U. S. A. Production Company, a division of Chevron U. S. A. Inc., as operator of the proposed stratigraphic test described above, hereby requests an exception to the State location requirements.

The proposed location for the well classified as a stratigraphic test is identified and described in caption and on the plats attached as Exhibits "A" and "B", copies of which were attached to the Application for Permit to Drill submitted to the BLM and the State of Utah on March 15, 1995.

The expected objective for drilling the Sevier Lake Federal 1-29 is to obtain stratigraphic information. Chevron's geologic purpose in locating the test in the SWSENE of Section 29 is to gain geologic and stratigraphic information from a complete suite of slimhole logs. Chevron finds it necessary to select this location in order to avoid possible fault complications that are indicated by seismic data.

There are no residents, surface owners or owners of offset wells within a 460 foot radius of the proposed site from which we need to obtain written consent.

Chevron requests your consideration in granting this exception location. If we can provide additional information to support this exception location, please do not hesitate to contact this office. (713)754-7659.

Amnette Bak Landman


attachments via fax delivery 4/27/95


Form 3160-3 (July 1992)

95

	(Other instructions on	OMB NO. 1004-0136
UNITED STATES	reverse side)	Expires: February 28, 19
P 1 7 SPENANT OF THE INTERIOR		I THATE DESIGNATION AND SER

	TYRYAK I	MENT OF THE	INIEKI AGEMENT	JK	İ	USA UTU-72587	
BUREAU OF LAND MANAGEMENT  APPLICATION FOR PERMIT TO DRILL OR DEEPEN						6. IF INDIAN, ALLOTTER OR TRIPE NAME	
CONTRACTOR CONTRACTOR	CATION	OH PERMIT I	DHILL	ON DEEL WIT		N/A	
3 1 LW 100 W 10 W 10 W 10 W 10 W 10 W 10		DEEPEN	1 🗆			7. UNIT AGREEMENT NAME N/A	
TTPE OF WELL		Stratigraph		MCCT	PLE []	8. FARM OR LEASE NAME WELL NO.	
FELL W	ELL   0T	HER Test	ZONE division	of Chevron		SEVIER LAKE FEDERAL 1-	
	. Producti	on Company, $\overset{a}{U}$	S.A. Inc			9. AR WELLING.	
DORESS AND TREEHIONS NO.		1635, Housto			_	10. FIRLD AND POOL, OR WILDCAT	
	(713) 75	4-7659	mith and Stat	a regularments *)		WILDCAT	
t wiir.oce					-	11. BSC., T., R., M., OR BLK.	
		TION 29, T19S	-KIUW			SEC. 29, T195-R10W, SLM	
At proposed prod. zon (SAME)						12. COUNTY OR PARISH   18. STATE	
DISTANCE IN MILES	NO DIRECTION PR	OM NEAREST TOWN OR	Post OFFICE*		Ì		
APPROX. 3/4 M	11 SE OF HW	IY 6/50	1 16 40 4	F ACRES IN LEASE	17. NO. OF	ACRES ASSIGNED	
DISTANCE FROM PROPU LOCATION TO NEAREST	4580' E	AST OF SEC.		025.68	TO TH	160 AC	
PROPERTY OR LEASE I	. unit line, if any			JZD.00	20. ROTAR	T OR CABLE TOOLS	
DISTANCE PROM FROM TO MEAREST WELL, D OR APPLIED FOR, ON TH	OMED LOCATION- RILLING, COMPLET IS IRASE, PT.	ED. N/A	7,00	00'	ROTA		
ELEVATIONS (Show wh						22. APPROX, DATE WORK WILL START	
4555' GL						4/30/95	
				A. COMPUNE BOACE	A.M		
		PROPOSED (	ASING AND	EMENTING PROOK			
	68AD6, \$28 0F C	<del></del>		BETTING DEPTH		QUANTITY OF CEMENT	
GIZE OF HOLE	13.375", 1	ASINO   WEIGHT P	ER FOOT	SETTING DEPTH	FROM	SURFACE	
		ASINO   WEIGHT P	ER FOOT	SETTING DEPTH	FROM S	SURFACE RF W// 313 CF	
17.5" 12.25"	13.375", L 9.625", K-	48.0 #/F	I 36th	50' 1000'	FROM S TO SUI (265 Sidered	SURFACE  RF W/ 313 CF  SX)  to be the Operator of	
Be advised to Chevron Seviunder the telands.  Bond coverage	13.375", L 9.625", K- hat Chevroi er Lake Fed rms and con	48.0 #/F 48.0 #/F 29.2 #/F 10.5.A. Productions of the	iction Co Millard C ne lease	mpany is conso., Utah, Leafor the opera	FROM STO SUIT (265 Stidered ase USA-lations conditions	SURFACE  RF W/ 313 CF  SX)  to be the Operator of U72587, and is responsite on the leased  -89-75-81-34 (Standard on U.S.A. Inc., as	
17.5" 12.25"  Be advised to Chevron Seviunder the tellands.  Bond coveragoil Company co-principal	13.375", 19.625", K- hat Chevror er Lake Fer rms and cor e for this of Califor s) via sur	48.0 #/F 48.0 #/F 55 48.0 #/F 29.2 #/F  10.S.A. Productions of the series of the series with t	iction Co Millard Co Me lease ided by N Molly own Sprovide	mpany is conso., Utah, Leafor the operationwide Boried subsidiary	FROM STO SUIT (265 State and No. Up Chevro CFR 3104	SURFACE RF W/ 313 CF SX)  to be the Operator of U72587, and is responsite onducted on the leased  -89-75-81-34 (Standard n U.S.A. Inc., as .2.	
Be advised to Chevron Seviunder the telands.  Bond coveragoil Company co-principal  ABOVE SPACE DESCRIPTION OF PARTY CONTRACT A BAK  (This space for Fee	13.375", 19.625", K- hat Chevror er Lake Fer rms and cor e for this of Califor s) via sur	48.0 #/F 48.0 #/F 55 48.0 #/F 29.2 #/F  10.5.A. Productions of the second secon	iction Co Millard Co Me lease Molly own s provided	mpany is conso., Utah, Leafor the operated subsidiary and for in 43 to depths. Give blowous pre	FROM STO SUI (265 Sidered ase USA-lations of the control of the co	SURFACE RF W/ 313 CF SX)  to be the Operator of U72587, and is responsite onducted on the leased  -89-75-81-34 (Standard n U.S.A. Inc., as .2.	





## LOCATION MAP

N89° 23'55" E 2,646.57' = Measured Bearing and Distance (N 89°12' E 2,640.0') = RECORD BEARING AND DISTANCE

9 500 1000 1500 SCALE: 1' = 1000' U.S. SURVEY FOOT

(N 89°12' E 2,64

MAGNETIC DELINATION = 16'15' EAST
Basis of Bearing
Geodetic North ©
Black USC&GS 1957
N=039°02'51.342"
W=112°54'54.0526"



SURVEYED UNDER MY DIRECTION

C:\SURVEY\SEVIER\S29PLAT.DWG PLOT: STANDARD.PCP

APPLICATION FOR PERMIT
TO DRILL
CHEVRON PRODUCTION CO.
SEVIER LAKE FEDERAL
1-29 WELL
2,250' FNL, 701' FEL
SE1/4 OF NE1/4 SEC 29
T.19 S., R.10 W., SLB&M
MILLARD COUNTY, UTAH

REDCON INC.
655 EAST MEDICAL DRIVE, SUITE 150
BOUNTIFUL, UTAH 84010
(801) 298-2401 FAX (801) 298-2024
Drawn By: KAP Date: MARCH 10, 1994
Bevised: Date:

CONFIDENTIAL

NAD 1927

**EXHIBIT 'B' - LOCATION PLAT** 

## STATE OF UTAH

Operator: CHEVRON USA INC | Well Name: SEVIER LAKE FED. 1-2
Project ID: 43-027-30035 | Location: SEC. 29 - T198 - R10W

Design Factors: Design Parameters: Collapse : 1.125 psi/ft Mud weight (9.00 ppg) : 0.468 : 1.00 Shut in surface pressure : 2791 psi Burst : 1.80 (J) 8 Round Internal gradient (burst) : 0.069 psi/ft : 1.60 **(J) Buttress** Annular gradient (burst) : 0.000 psi/ft Other : 1.50 (J) Tensile load is determined using buoyed weight Body Yield : 1.50 (B) Service rating is "Sweet"

	Length (feet)	Size (in.)	Weight (lb/ft)	Grade	e Join		Depth (feet)	Drift (in.)	Cost
1	1,000	9.625	36.00	K-55	5 ST&C		1,000	8.765	
	Load (psi)	Collapse Strgth (psi)	S.F.	Burst Load (psi)	Min Int Strgth (psi)	Yield S.F.	Load (kips)	Tension Strgth (kips)	S.F.
1	468	2020	4.321	2860	3520	1.23	31.05	423	13.62 J

Prepared by: FRM, Salt Lake City, UT

Date : 0

06-06-1995

Remarks

Minimum segment length for the 1,000 foot well is 1,000 feet.

SICP is based on the ideal gas law, a gas gravity of 0.69, and a mean gas

temperature of 109°F (Surface 74°F , BHT 144°F & temp. gradient 1.000°/100 ft.)

Surface/Intermediate string:

Next string will set at 7,000 ft. with 9.00 ppg mud (pore pressure of 3,273 psi.) The frac gradient of 1.000 psi/ft at 7,000 feet results in an injection pressure of 7,000 psi Effective BHP (for burst) is 2,860 psi.

NOTE: The design factors used in this casing string design are as shown above. As a general guideline, Lone Star Steel recommends using minimum design factors of 1.125 - Collapse (with evacuated casing), 1.0 - Burst, 1.8 - 8 Round Tension, 1.6 - Buttress Tension, and 1.5 - Body Yield. Collapse strength under axial tension was calculated based on the Westcott, Dunlop and Kemler curve. Engineering responsibility for use of this design will be that of the purchaser. Costs for this design are based on a 1987 pricing model. (Version 1.06)

#### ·. 01

## LONE STAR STEEL COMPANY Fax Cover Sheet

DATE:

June 6, 1995

TIME:

3:24 PM

TO:

Frank Mathews

PHONE:

801 538 5340

State of Utah

FAX:

801 359 3940

FROM:

Beau Urech

PHONE:

FAX:

800 527 4615

L\$\$

214 770 6448 214 770 6409

RE:

9-5/8" 29.30# K55 STC

Number of pages including cover sheet: 2

## Message

The above item is nonstandard for casing and line pipe. Calculations for properties based on my best guess of wall thickness are attached.

ូរុបN-06-95 TUE 14 ្វែ

# LONE STAR STEEL COMPANY Product Specification 9.625" 29.30# (.281" wall) K-55 STC

Grade	K55
Mechanical Properties	
Yield Strength	
Minimum	55 ksi
Maximum	80 ksi
Tensile Strength	
Minimum	95 ksi
Dimensions	
Outside Diameter	9.625 in.
Nominal Wall Thickness	0.281 in.
Nominal Weight	29.30 lbs/ft
Plain End Weight	28.07 lbs/ft
Cross-sectional Area	8.249 sq. in.
Inside Diameter	9.063 in.
Drift Diameter	8.907 in.
Performance Ratings	
Minimum Collapse	1,220 psi
Minimum Internal Yield Strength	2,810 psi
Pipe Body Yield Strength	454 kips
STC Joint Strength	319 kips



Western Exploration Division

## **FAX COVER LETTER**

## WESTERN EXPLORATION DIVISION

18TH FLOOR - CHEVRON TOWER HOUSTON, TEXAS

FAX TELEPHONE # (713) 754-7854

PLEASE DELIVER TO:
FRANK MATTHEWS
STATE OF UTAH
FAX #: 801) 359 3940
COMMENTS: EIGHT POINT DRILLING PLAN
TONI STATE TONI
(UPDATED 4/27/95) FOR SETTER LAKE
(UPDATED 4/27/95) FOR SELIED LAKE
# OF PAGES INCLUDING COVER SHEET

IF ALL THE PAGES ARE NOT RECEIVED, PLEASE CONTACT US ASAP.

FROM: AUNFITE BAK

Phone #: (713) 754- 7659

#### CHEVRON USA PRODUCTION CO.

SEVIER LAKE FEDERAL #1-29 700' FEL & 2250' FNL SEC 29-T19S-R10W MILLARD COUNTY, UTAH

### **EIGHT POINT DRILLING PLAN**

Updated 4/27/95

## 1. ESTIMATED FORMATION TOPS:

Ancient Laké Bonneville Sediments	Şurface
Tertiary Valley Fill	Near Surface
Tertiary Basalt	1,400′
Tertiary Valley Fill	1,500'
Pre-Tertiary	2,500'
Precambrian	7,000'

## 2. ESTIMATED DEPTHS OF TOP AND BOTTOM OF WATER, OIL, GAS, OR OTHER MINERAL BEARING FORMATIONS AND PLAN FOR PROTECTION:

**Deepest Fresh Water:** ~700' based on depth of existing water wells in area used for the purpose of watering livestock.

Oil Shale: None Expected.

Oil: Possible oil below the Tertiary Basalt.

Gas: Possible gas below the Tertiary Basalt.

Protection of oil, gas, water, or other mineral bearing formations: Protection shall be accomplished by cementing surface casing back to the surface or to depths sufficient to isolate required formations. This well is a stratigraphic test and will be plugged and abandoned upon completion of drilling and logging operations. There is no intent to produce this well. Please refer to casing and cement information for protection plans.

## 3. PRESSURE CONTROL EQUIPMENT:

For drilling conductor hole to 50': No BOP equipment required.

For drilling surface hole to 1,000':

No BOP equipment required. Rotating head for air drilling only.

For drilling through 9.625" surface casing to TD:

Maximum anticipated surface pressure is <2590 psi.

Pressure control equipment shall be in accordance with BLM minimum standards for 3000 psi equipment and will include a remote operated choke.

A casing head with an 11", 3000 psi flange will be screwed or welded onto the 9.625" surface casing.

BOP stack will consist of a double gate and annular preventer. The double gate will be equipped with pipe rams on bottom and blind rams on top. The choke and kill lines will be connected to outlets between the bottom and top rams, utilizing either the ram body outlet or a drilling spool with side outlets. The BOP stack will be 9" or 11" bore, 3000 psi working pressure or greater. The choke and kill lines will be 2" or 3" bore, 3000 psi working pressure or greater. Please refer to attached schematics.

A rotating head will be used while drilling below surface casing to facilitate using air, air/mist, stiff foam or aerated mud as a circulating medium.

Test procedure and frequency shall be in accordance with BLM minimum standards for 3000 psi equipment.

## 4. SUPPLEMENTAL DRILLING EQUIPMENT AND CASING INFORMATION:

Casing Information: All casing except 13 3/8" will be new pipe and tested to 1500 psi. The 13 3/8" will not be tested.

Casing	Weight	Grade	Conn.	Stage	Centralizers
13.375"	48.0 #/ft. 36#/s/	H-40	STC	No	No
9.625"	36# JE	K-55	STC	No	*

<sup>\*</sup> Centralizers will be placed 10' above shoe, on 1st, 3rd, 5th and last collars.

## Casing Design Information (13 3/8" casing @ 50'):

Collapse value for new pipe: 770psi	Actual Load: 23psi	S.F.: .03
Burst value for new pipe: 1730psi	Actual Load: 23psi	S.F.: .01
Tension value for new pipe: 322,000#	Actual Load: 2400#	S.F.: ,01
(9 5/8" casing @ 1,000'):		
Collapse value for new pipe: 2020psi	Actual Load: 468psi	S.F.: .23
Burst value for new pipe: 3520psi	Actual Load: 2208psi	S.F.: .63
Tension value for new pipe: 423,000#	Actual Load: 36,000#	S.F.: .09

#### Cement Information:

Casing	Cement
13.375"	Cemented from surface utilizing Ready-Mix.
9.625"	Oilfield type cement circulated in. Class "A" w/ 2% CaCl <sub>2</sub> single slurry mixed to 15.6 ppg, yield = 1.19 cf/sx. Fill to surface with 313 cf (265 sx) calculated. Tail plug used. Allowed to set under pressure.

Upon completion of drilling and logging operations, well will be abandoned. Abandonment plugs will be of Class "A" neat slurry. Size and location of plugs will be determined at conclusion of logging.

## **Drilling Equipment:**

Conductor hole will be drilled and conductor casing set with small rotary surface hole rig.

Drilling the surface hole below conductor casing will be with a small rotary rig equipped to use air, fluid or a combination of both. Hole size will be in the 12 1/4" - 11" range at the discretion of the drilling contractor.

Drilling below surface casing will be with conventional rotary equipment utilizing air, fluid or a combination of both. Hole size will vary between 8 3/4", 8 1/2" and 7 7/8" depending on hole conditions.

## 5. CIRCULATING MEDIUM, MUD TYPE, MINIMUM QUANTITIES OF WEIGHT MATERIAL, AND MONITORING EQUIPMENT:

Surface hole will be drilled with air, air/mist, foam, or mud depending on hole conditions. Drilling below surface casing will be with air, air/mist, stiff foam or aerated water based drilling fluids consisting primarily of fresh water, bentonite, lignite, caustic, lime, soda ash, and polymers. No chromate's will be used. It is not intended to use oil in the mud, however, in the event it is used, oil concentration will be less than 4% by volume. Maximum anticipated mud weight is ±9.0 ppg.

No minimum quantity of weight material will be required to be kept on location. Sufficient quantity of water to load the hole while air drilling will be on location and readily available at all times.

PVT/Flow Show will be on location and operable from base of conductor casing to TD in the event fluid drilling is incorporated.

Gas detector will be used from surface (depth mud loggers on) to TD.

## 6. ANTICIPATED TYPE AND AMOUNT OF TESTING, LOGGING, AND CORING:

## Logging:

Mud logging:

Electric Logging:

Surface to TD

A complete suite of open hole

logs will be run.

Coring:

None planned but are possible.

Testing:

None planned but are possible.

# 7. EXPECTED BOTTOM HOLE PRESSURE AND ANY ANTICIPATED ABNORMAL PRESSURE, TEMPERATURES, OR OTHER HAZARDS (H<sub>2</sub>S, STEAM, ETC.) AND ASSOCIATED CONTINGENCY PLANS:

Normal pressure gradient to TD. Some slightly pressured gas zones (.45-.47) may exist below the Tertiary Basalt. All zones are anticipated to be tight - drill underbalanced with air, air/mist, stiff foam or aerated fluids. If any Hydrogen Sulfide/Steam is encountered, air drilling will be discontinued and drilling mud will be used exclusively from that point to completion of the well

Maximum expected BHP @ 7000':

~3290 psi (0.47 psi/ft.).

Maximum expected BHT @ 7000':

~1350 F


### 8. OTHER:

If large quantities of water are encountered during air drilling operations, any clear fluid containing no solids or hydrocarbons will be spread on location and neighboring dirt/gravel roads in an effort to control dust.

# CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL-CONTROL AND BLOWOUT PREVENTION

#### E. CLASS III BLOWOUT PREVENTER STACK:

The Class III preventer stack is designed for drilling or workover operations. It is composed of a single hydraulically operated annular preventer on top, then a blind ram preventer, a drilling spool, and a single pipe ram preventer on bottom. The choke and kill lines are installed onto the drilling spool and must have a minimum internal diameter of 2". All side outlets on the preventers or drilling spool must be flanged, studded, or clamped. An emergency kill line may be installed on the wellhead. A double ram preventer should only be used when space limitations make it necessary to remove the drilling spool. In these instances, the choke manifold should be connected to a flanged outlet between the preventer rams In this hookup, the pipe rams are considered master rams only, and cannot be used to routinely circulate out a kick. The Class III blowout preventer stack is shown to the right in Figure 11J.4.




のでは、100mmの

## CHEVRON DRILLING REFERENCE SERIES VOLUME ELEVEN WELL CONTROL AND BLOWOUT PREVENTION

#### D. TYPE "B" KILL LINE --- CLASS III, IV , AND V WELLS

The type B kill line described below in Figure 11J.11 is the minimum recommended hookup for installation on all Class III, Class IV and Class V wells. Specific design features of the type B kill line include:


- 1. The preferred kill line connection to the well is at the drilling spool, however, a preventer side outlet may be used when space restrictions exclude the use of a drilling spool. In all cases, the kill line must be installed below the uppermost blind rams so the well can be pumped into with no pipe in the hole.
- 2 The arrangement includes two 2" (nominal) gate valves installed at the drilling spool and an upstream fluid cross. The outside valve may be hydraulically remote controlled.
- 3. Two pump-in lines should be attached to the fluid cross. The primary kill line should be routed to the rig standpipe where it can be manifolded to the rig pumps. The remote kill line should be run to a safe location away from the rig or to the rig cementing unit. The remote kill line should have a loose end connection for rigging-up a high pressure pumping unit.
- 4. Both the primary kill line and the remote kill line must include a 2" check valve which is in working condition while drilling. If a check valve is crippled for testing purposes, the flapper or ball must be re-installed and tested before drilling resumes.
- 5. The primary kill line must include a pressure gauge which can display the pump-in pressure on the rig floor.
- 6. Any lines which are installed at the wellhead are designated as "emergency kill lines" and should only be used if the primary and remote kill lines are inoperable.



4:

## CHEVRON USA PRODUCTION COMPANY TENTATIVE RIG/LOCATION PLAT

MAP SHOWING TENTATIVE RIG/FACILITIES LOCATION DETAILS SEVIER LAKE FEDERAL #1-29





DIVISION OF OIL, GAS AND MINING

Ted Stewart **Executive Director** James W. Carter Division Director 801-538-5319 (TDD)

355 West North Temple 3 Triad Center, Suite 350 Salt Lake City, Utah 84180-1203 801-538-5340 801-359-3940 (Fax)

June 6, 1995

Chevron U.S.A. Production Company P. O. Box 1635 Houston, Texas 77251

Federal 1-29 Well, 2250' FNL, 700' FEL, SE NE, Sec. 29, T. 19 S., R. 10 W., Re: Millard County, Utah

#### Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-027-30035.

Sincerely.

Associate Director

ldc

**Enclosures** 

Millard County Assessor

Bureau of Land Management, Richfield District Office

**WAPD** 



Operator: _	Chevron	<u>U.S.A.</u>	Product	ion Co	mpany		
Well Name &	Number:	Fee	deral 1-2	29			
API Number:	43-02	<del>7-30035</del>	)				
Lease:U	TU-72587						
Location:	SE NE	Sec.	29	_ T	19 S.,	_ R	10 W.

## **Conditions of Approval**

## 1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements

Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.



## DIVISION OF OIL, GAS AND MINING

## SPUDDING INFORMATION

Name of C	Company: <u>CHEVRON USA</u>		
Well Name	e: SEVIER LAKE 1-29		
Api No	43-027-30035		
Section_	29 Township 19S	Range <u>10W</u>	County MILLARD
Drilling	Contractor APOLL	0	
Rig #	57		
SPUDDED:	Date 6/26/95	_	
	Time	_	
	How_ROTARY	_	
Drilling	will commence		·····
Reported	by D. HACKFORD-DOGM		_
Telephone	= #		
Date:	6/29/95	Signed:	FRM

From:

David Hackford

To:

**FMATTHEWS** 

Date:

Tuesday, June 27, 1995 10:37 am

Subject:

CHEVRON

KEN JAPP JUST CALLED ME AND SAID THEY DRY SPUDDED THE SEVIER LAKE FED. 1-29 ON 6/21/95 AND ROTARY SPUDDED TODAY, 6/26/95, WITH KENTING APOLLO RIG #57. THIS IS IN MILLARD COUNTY AND I DON'T HAVE THE LEGALS OR API.

Form 3160-5 (June 1990)

#### TTED STATES DEPART MENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT**

#### FORM APPROVED

Budget Bureau No. 1004-0135

Expires: March 31, 1993

5. Lease Designation and Serial No.

6. If Indian, Allottee or Tribe Name

## **USA UTU-72587**

SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.

USE "APPLICATION FOR PERMIT -" For such proposals N/A 7. If Unit or CA, Agreement Designation SUBMIT IN TRIPLICATE 1. Type of Well N/A 8. Well Name and No. Oil Well ☑ Gas Well ☐ Other 2. Name of Operator SEVIER LAKE FEDERAL 1-29 CHEVRON U.S.A. PRODUCTION COMPANY 9. API Well No. 43-027-30035 3. Address and Telephone No. 10. Field and Pool, or Exploratory Area P. O. BOX 4876 ATTN: MARY COHLMIA **WILDCAT** HOUSTON, TX 77210 (713)754-5068 11. County or Parish, State 4. Location of Well (Footage, Sec., T., R., M., or Survey Description) 2250' FNL, 700' FEL MILLARD CO., UTAH SEC 29, T19S, R10W

12 CHECK APPROPRIATE	<b>BOX(s) TO INDICATE NATURE OF N</b>	OTICE, REPORT, OR OTHER DATA
TYPE OF SUBMISSION	TY	PE OF ACTION
□ Notice of Intent		☐ Change of Plans
	☐ Recompletion	☐ New Construction
☑ Subsequent Report	☐ Plugging Back	☐ Non-Routine Fracturing
	☐ Casing Repair	☐ Water Shut-off
☐ Final Abandonment Notice	☐ Altering Casing	☐ Conversion to Injection
	Other	☐ Dispose Water
		(Note: Report results of multiple completions on Well
		Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations ( Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

THE PURPOSE OF THIS SUNDRY IS TO REPORT THE PLUGGING AND ABANDONMENT OF THE PLUGGING WAS WITNESSED BY THERON MITCHELL, BLM.

- 1. WELL WAS P&A'D ON 7/12/95.
- 2. CEMENT PLUGS:

PLUG #1 - FROM 5220'-5000' W/ 130 SKS. OF 'H' CEMENT

PLUG #2 - FROM 1705'-1500' W/ 170 SKS. OF 'H' CEMENT CONTAINING 2% CACL2

PLUG #3 - 50 SKS. AT SURFACE

DIV. OF OIL. GAS & MINING

3-BLM RICHFIELD, 1-RODY COX, BLM-FILLMORE,

1-AL MCKEE, BLM-SALT LAKE CITY, 1-FRANK MATTHEWS, ST OF UTAH, 1-A. BAK, CHEVRON LAND, DRLG

14. I hereby certify that the foregoing is true and correct.  Signed: North Control of the Contr	Title: DRLG. TECHNICAL ASSIST.	Date:	7/18/95
(This space for Federal or State office use)			
Approved by:  Conditions of approval, if any:	Title:	Date:	

Title 18 U. S. C. Section 1001 makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Form 3 60-4

# UNITED ST TES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT

SUBMIT IN D' ATE\*
(See othe. uctions
on reverse side)

FOR APPROVED OMB NO. 1004-0137 Expires: December 31, 1991

5. LEASE DESIGNATION AND SERIAL NO.

WE	LL CC	MPI	ETION C	R RI	ECOM	PI ETIO	ND	FPODT /	NID	TOC*	6.	IF INDIAN		TEE OR TRIBE NAME
						LETIC	IVI	EIOKI	AND	LUG			N	√/A
ia. TYPE OF V		oil [	GAS ] [	<b>-</b>	DRY X						7.	UNIT AGE		=
b. TYPE OF COMPLETION:  8. FARM OR LEASE NAME, WELL NO														
NEW WORK DEEP- PLUG DIFF. OTHER Sevier Lake Federal #1-29														
	WELL OVER LEN BACK RESVR. L.  2. NAME AND OPERATOR  9. API WELL NO.													
CHEVRON U	I.S.A. PRO	DUCTIO	ON CO					CD (6) (E	3 57 5	2 <b>9</b> 5780 ET	- J-9.	API WELL		7-30035
3. ADDRESS AND TELEBRIONE NO.														
/														
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)														
At surface 2205' FNL & 700' FEL Section 29, T19S, R10W									Y/T		OR ARE			
At top prod.	interval repoi	rted below					DIV	OF OU C	` A ()	LIAIRA O	N.I.A.	Sec	tion 29,	T19S, R10W
				1	TIA		UIV.	OF OIL, O	CAE	& WHIE	f			
At total depth	١	~ 6	ITID	-V	\\ <del>\</del> ₽	PERMIT NO.	DA	TE ISSUED	112	COUNTY OR P	APICH			
	$\mathbf{C}$	1 1	ントリノ			43-027-30035		5/23/95	12.		Millard			13. STATE Utah
15. DATE SPUI 6/15/9		/10_DA	7/10/95			L. (READY TO P				DF, RKB, RT,	GR, ETC.	•	19. EL	EV. CASINGHEAD
20. TOTAL DEI		TVD				gged and Aba		11/14/12/	octario	4555' GR				4555'
	•		21. PLUG, BAC			22. IF MULT	TIPLE CO	MPL., HOW MAN	1Y?"	23. INTERVA		ROTAR	Y TOOLS	CABLE TOOLS
6014' MD 6014' TVD Plugged and Abandoned to Surface								6	6014°	0,				
24. PRODUCING INTERVAL(S), OF THIS COMPLETION - TOP, BOTTOM, NAME (MD AND TVD)*  25. WAS DIRECTIONAL SURVEY MADE?														
Dry Hole - Plugged and Abandoned														
26. TYPE ELECTRIC AND OTHER LOGS RUN								27.	VAS WELI	CORED				
Induction, Neutron, Density, Gamma Ray										DEWALL				
28.					CAS	ING RECORD (	Report all	l strings set in well)				7.4		
CASING 13 3/8" K-55	SIZE/GRADE		WEIGHT, LB	/FT.	DEPTI	H SET (MD)	247	HOLE SIZE		OP OF CEMENT,				AMOUNT PULLED
9 5/8" K-55	Surface - 14 yas Reduit								<u>0</u>					
7 Surface - 670 sxs Lite & 360 sxs Class H 0							<u> </u>							
29. LINER RECORD 30. TURING RECORD														
SIZE	TOP	(MD)	BOTTOM (N			CEMENT*		SCREEN (MD)		SIZE		UBING RE H SET (MD)		PACKER SET (MD)
							┼—							
31.	PERF	ORATION	RECORD (Interval)	size and n	umber)		32.	ACI	D, SHO	r, fracture.	CEMENT	SOUEEZI	E. ETC.	
31. PERFORATION RECORD (Interval, size and number)  32. ACID, SHOT, FRACTURE, CEI  Dry Hole - Plugged and Abandoned  DEPTH INTERVAL (MD)						AMOUNT AND KIND OF MATERIAL USED								
CONFIDENTIAL														
			UU	N/	IUC		Hi					<del></del>		
33. *						PRODUCT					· · · · · · · · · · · · · · · · · · ·	<del></del>		
DATE FIRST PRODUCTION PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump)  PRODUCTION METHOD (Flowing, gas lift, pumping - size and type of pump)  FLOWING							PRO	DUCING		ng or shut-in)				
DATE OF TEST	OF TEST HOURS TESTED CHOKE SIZE PROD'N FOR TEST PERIOD OIL-BBL. GAS-MCF.				Dry Hole - Plugged and Abandon WATER-BBL GAS-OI		GAS-OIL RATIO							
						$\rightarrow$		Ì	N	<b>ICF</b>				
FLOW, TUBING PR	ESS., C	ASING PRES	SURE	CALC	JLATED 24-HO	UR RATE		OIL-BBL.	GA	SMCF.	WAT	ER-BBL.	1 6	HL GRAVITY-API (CORR.)
PSI	PSI	I			$\rightarrow$									
34. DISPOSITION OF GAS (Sold, Used For Fuel, Vented, Etc.)  TEST WITNESSED BY								•						
35. LIST OF ATTACHMENTS														
36. I hereby cer	rtify that th	e foregoin	g and attached in	ormation	is complete	and correct as	determi	ned from all avai	lable so	corde			1 1	
SIGNED	M	1	$\mathcal{L}$		complete		_			vius.		DATE '	۱, ا ر	
ממוזמוני	<u> </u>					ITILE	<b>URK</b>	sens En	٤.		1	DATE	~131	<b></b>

37. SUMMARY OF POR drill-stem tests, inclur recoveries):	(OUS ZONES: (	Show all important al tested, cushion u	SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals; and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries):	38. GE	GEOLOGIC MARKERS	
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.		TOP	П
			No porous zones encountered	NAME	MEAS. DEPTH	TRUE VERT. DEPTH
				Lake Bonneville Sediments Tertiary Paleozoic Carbonates, probably middle Cambrian	Surface 1370 5160	1370 5160
						_
						<u> </u>




## Chevron U.S.A. Inc.

# Transmittal of Confidential Data

**Exploration, Land & Production** 

DATA TRANSMITTAL RECORD

			430					
SAL	pt. of NATURAL RESOURCES OF OIL, GAS, and Mining 14 WEST NORTH TEMPLE Suiteland TLAKE CITY, UT 84114-5801 icky Dyson	Requested By: Telephone  Reference No.  Date Requested	SFIDENTIAL					
Shipped Via		Way Bill No.:	Date:					
Quantity	D	escription						
		31Ack Rock Fed. 29 43027.						
	1 Dipole Shows 1 Litho Denisty C	Comp. New. /GR 1 - Bowh	ale Comp. Sonie w/Com					
			N. New. Litho Courty / GR					
	1 Mud Log 1 Phoses Induction 1 Strat. High Res	on w/CR 1-Duas Dipmeter	Laterlog W/GR					
SEVIER LAKE - Chevron USA Sevier Lake Feb. #1-29 *195-10W-29 4302730035								
······································	Run 1							
	1 Dual Dipmeter Monitor Log							
	1 Qual Induction - SFL							
	1 Comp. Deutson-Litho-Density							
	1 Long Spacing Sonie Log							
	1 Mid Log)							
☐ Data are	to be returned to this office	not to be returned to this office						
Data are to be returned to this office  Please Acknowledge Receipt and Return Yellow Copy								
Received By	:		Date:					
CC To: Approved By:								
		•	; ;					





Chevron U.S.A. Production Company Western Exploration Division P.O. Box 1635 Houston, TX 77251

May 19, 1997



Department of Natural Resources Division of Oil, Gas and Mining Attention: Vicky Dyson 1594 West North Temple, Suite 1210 Salt Lake City, Utah 84114-5801

Re:

Sevier Lake Federal #1-29, API No. 43-027-30035

195 100 29

Submittal of Logs and Request To Hold Confidential

Dear Ms. Dyson:

Enclosed herewith are the logs you requested in your letter of April 9, 1997, to Kevin M. Kopp, in our Evanston office, for the captioned well. In accordance with Oil and Gas General Rule R649-2-11, we hereby request that the logs we have marked as privileged and/or confidential, be held confidential for the maximum length of time provided.

If you have any questions, please contact the undersigned at (713) 754-3826.

Singerely,

Douglas A. Brown